

Project Overview Documents

MUSE Project Management
Project Organizational Chart
Time Commitment of Senior Personnel
WBS Dictionary and summary
Cost Summary
Summary of Travel costs
Schedule (Gantt chart)
Risk Assessment
Summary of Specs and Quality Control
WBS individual details
Contingency Guidelines
Risk Assessment Guidelines

MUSE PROJECT MANAGEMENT

1. Description of the research objectives motivating the facility proposal
2. Comprehensive statement of the science requirements to be fulfilled by the proposed facility (to the extent possible identifying minimum essential as well as desirable quantitative requirements), which provide a basis for determining the scope of the associated infrastructure requirements;
3. Description of the Educational Outreach and Broader Societal Impacts associated with the purpose of the facility, including the scope of work, budget and schedule.
4. Description of the infrastructure necessary to obtain the research and education objectives
5. Work breakdown structure (WBS)
6. Work breakdown structure dictionary defining scope of WBS elements
7. Project budget, by WBS element
8. Description of the basis of estimate for budget components
9. Project risk analysis and description analysis methodology
10. Contingency budget and description of method for calculating contingency
11. Project schedule (and eventually a resource-loaded schedule)
12. Organizational structure
13. Plans and commitments for interagency and international partnerships
14. Acquisition plans, sub-awards and subcontracting strategy
15. Project technical and financial status reporting, function of the PMCS, and description of financial and business controls
16. Project governance
17. Configuration control plans
18. Contingency management
19. Internal and institutional oversight plans, advisory committees, and plans for building and maintaining effective relationships with the broader research community that will eventually utilize the facility to conduct research
20. Quality control and quality assurance plans
21. Environmental plans, permitting and assessment
22. Safety and health issues
23. Systems engineering requirements
24. Systems integration, testing, acceptance, commissioning and operational readiness criteria
25. Plans for transitioning to operational status
26. Estimates of operational cost for the facility

1. Description of the research objectives motivating the facility proposal

The objective of this proposal is to measure cross sections for elastic scattering from the proton of electrons and negative muons, and positrons and positive muons, using the same apparatus. The cross sections will be used to compare electron to muon scattering, positive polarity to negative polarity scattering, and to extract the proton radius. The goal is for generally sub-percent level uncertainties, allowing the proton radius to be extracted with a combined systematic and statistical uncertainty of about 0.012 fm for both the muon and electron.

The proton charge radius can be determined by scattering charged leptons from protons, or by measuring the Lamb shift in hydrogen or muonic hydrogen. The radius determined from the scattering of electrons and Lamb shift in hydrogen are in good agreement, with values of 0.8791 ± 0.0079 fm and 0.8758 ± 0.0077 fm, respectively. The most precise measurement from muonic hydrogen of 0.84087 ± 0.00039 fm disagrees with the electron based measurements by about $7\alpha\mu\gamma\iota\sigma$. No accepted explanation has yet been found. This discrepancy, along with the muon g-2 discrepancy and the cosmic positron excess, gives hints of new physics. No measurement of the radius using muon scattering exists.

2. Comprehensive statement of the science requirements to be fulfilled by the proposed facility (to the extent possible identifying minimum essential as well as desirable quantitative requirements), which provide a basis for determining the scope of the associated infrastructure requirements;

In order to resolve the discrepancy, the facility must be able to measure the scattering of muons and electrons at the sub-percent level. In order to study possible two-photon exchange effects, measurements using scattering of both positive and negative muons, as well as positrons must be done. The critical elements are: hydrogen target, particle identification, good scattering angle determination, high tracking efficiency, and a data acquisition rate of about 2 kHz with dead-time of 15% or less.

These elements led to the following design elements:

- (1) A liquid hydrogen target to ensure adequate rate and low background (rather than CH₂ which requires a large background subtraction).
- (2) Particle ID: The beam is a mixture of electrons, muons, and pions. Particle ID can be achieved by a combination of timing relative to the accelerator RF and time of flight measurements. Cerenkov and scintillating fiber detectors provide the needed timing. The good time resolution of the Cerenkov detectors allows suppression of events from muons in the beam decaying into electrons (and undetected neutrinos). Scintillation detectors for the scattered particles are needed to cleanly identify scattered particles and trigger the data acquisition.
- (3) Scattering angle: The divergence of the beam is sufficiently large that tracking of the incident beam particles is needed to adequately determine the scattering angles. GEM detectors provide this measurement. The scintillating fiber tracking allows separation of multiple tracks by timing. The outgoing scattering angle is determined by a straw tube

chamber. The straw tubes have good resolution and the multiple layers provide high efficiency.

3. Description of the Educational Outreach and Broader Societal Impacts associated with the purpose of the facility, including the scope of work, budget and schedule.

The broader impact of this project is primarily in the training of students and young scientists, at the undergraduate, graduate, post-doctoral, and junior faculty levels. The institutions involved in this project have trained large numbers of students of each type, including from minority populations. The training they have received in the process of doing basic research has led to careers in a variety of areas, from medical physics to national security, in addition to continuing to work in fundamental physics research. The MUSE experiment will broaden the perspective of American students by having them work in an international collaboration at an international laboratory, which will prepare them effectively to become prominent global scientists of the next generation. With the broad interest in the proton radius puzzle, MUSE has the potential to be broadly inspirational beyond the current scientific community.

4. Description of the infrastructure necessary to obtain the research and education objectives

The infrastructure consists of the π M1 beam-line at PSI and the detector assembly described above. The PSI beam-line provides a mixed particle beam, with a momentum range of 100-500 MeV/c.

5. Work breakdown structure (WBS)

The MUSE project consists of several fairly self contained elements, which form the natural basis for the WBS. The WBS is shown in the table below. Each WBS, except for WBS 9 corresponds to a detector/subsystem needed for the detector. WBS 9 relates to the integration and testing of all elements at PSI.

| WBS # | Title | Manager |
|-------|---------------------|---------|
| 1 | Frames & Design | Gilman |
| 2 | Scintillating Fiber | Ron |
| 3 | Cerenkov | Gilman |
| 4 | Straw Chambers | Ron |
| 5 | Cryo-target | Briscoe |
| 6 | Electronics | Downie |
| 7 | Scintillators | Strauch |
| 8 | GEM | Kohl |
| 9 | Installation | Gilman |

6. Work breakdown structure dictionary defining scope of WBS elements

See attached document.

7. Project budget, by WBS element

See attached document.

8. Description of the basis of estimate for budget components

Each WBS will have list of components and basis of estimate. A summary is attached.

9. Project risk analysis and description analysis methodology

We will base the risk analysis on techniques described in the PBMOK 3rd Edition.

10. Contingency budget and description of method for calculating contingency

We will be guided by the FNAL system as applied to MINERvA. See attached document. A significant part of the budget is related to purchase of components in Europe and travel to Europe, giving an uncertainty in currency exchange rate. For purposes of this project, we have assumed a first year exchange contingency of 10% and 15% for the subsequent years. Travel costs contingency is assumed at 10% for the first year, with an additional 5% per year to account for inflation. 10% contingency is also estimated for uncertainty on time needed for set-up and running the experiment.

11. Project schedule (and eventually a resource-loaded schedule)

See attached document.

12. Organizational structure

The overall guidance of the experiment is given by the spokespersons: R. Gilman (Rutgers), E. Downie (GWU), and G. Ron (Hebrew University). The construction project will be led by R. Ransome (Rutgers) and W. Briscoe (GWU). The WBS breakdown with WBS managers is given in the attached organizational chart.

13. Plans and commitments for interagency and international partnerships

The experiment will take place at the Paul Scherrer Institute, Villigen Switzerland. The laboratory's commitment will be the installation of the beam line and associated hardware/software, maintenance of the liquid hydrogen target, and providing the beam. A commitment letter is attached.

14. Acquisition plans, sub-awards and subcontracting strategy

Purchase of either off-the-shelf items or specialty components is detailed in the BOE documents associated with each WBS. There will be no subcontracting.

15. Project technical and financial status reporting, function of the PMCS, and description of financial and business controls

Financial reports will be submitted to the Project Manager. The technical status will be reported to and reviewed by the Spokespersons and Project Manager.

16. Project governance

The Project Manager and assistant Project Manager will govern the project, with full consultation of the spokespersons and WBS managers.

17. Configuration control plans

All changes in scope with cost variance greater than \$5000 or time to completion variance greater than 4 weeks must be submitted to Project Manager for review. Any change in scope with significant impact on the physics goals must be reviewed and approved by Project Manager and Spokespersons.

18. Contingency management

Contingency reserves will be determined through an analysis of the risks and contingency estimates of each WBS. The Project Manager will have the responsibility for allocation of reserves. Contingency of less than \$5000 will be at the discretion of each WBS manager. The Project Manager will consult with all WBS managers for any allocation request greater than \$25,000, but will have final say on all allocations.

19. Internal and institutional oversight plans, advisory committees, and plans for building and maintaining effective relationships with the broader research community that will eventually utilize the facility to conduct research

N/A.

20. Quality control and quality assurance plans

Each WBS will list quality control plan. See attached document for a summary of each WBS.

21. Environmental plans, permitting and assessment

N/A.

22. Safety and health issues

The project construction does not involve the use of exceptionally hazardous materials or work conditions. The construction will take place primarily at university laboratories. All university safety requirements will be met. The primary safety hazard is the cryogenic target.

23. Systems engineering requirements

These are described in items 24 and 25 below.

24. Systems integration, testing, acceptance, commissioning and operational readiness criteria

1. Detectors all connected to DAQ, read out, and decoded successfully, with

trigger functioning at level to read out detectors.

2. Various calibrations runs and performance confirmed, at least at low rates


- a) beam Cerenkov efficiency and timing
- b) SciFi efficiency and time resolution, and alignment wrt GEMs
- c) GEMs read out in ~ 0.15 ms time scale, tracking efficiently, 3 hit events show < 100 μ m resolution
- d) Veto efficiency confirmed (can offset and put it in beam)
- e) Beam Monitor efficiency and time resolution confirmed
- f) STT position, track finding, and efficiency calibrated by measurements with STT rotated to be in beam.
- g) Scintillator plane performance check - pulse heights and timing - by running beam through them.
- h) Trigger performance checked with combination of real data and random signals.
- i) DAQ readout rate ability can be checked with pseduodata (pulser signals) and monitoring readout on scope.

25. Plans for transitioning to operational status

Follows from 24.

26. Estimates of operational cost for the facility

Cost to this project will be travel funds. Cost of running the beam and detectors will be paid by PSI.



Time Commitment of Senior Personnel – Year 1

| Institution | Name | Position | FTE | Responsibility |
|--------------------|-----------------|-----------------|------------|---------------------------------------|
| Rutgers | R. Gilman | Professor | 0.55 | Spokesperson, WBS 1,3 manager |
| Rutgers | R. Ransome | Professor | 0.20 | Project Manager |
| GWU | E. Downie | Asst. Prof. | 0.30 | Spokesperson, WBS 6 manager |
| GWU | B. Briscoe | Professor | 0.36 | Deputy Project Manager, WBS 5 manager |
| GWU | A. Afanasev | Professor | 0.20 | Theory support |
| S. Carolina | S. Strauch | Assoc. Prof. | 0.35 | WBS 7 manager |
| S. Carolina | R. Gothe | Professor | 0.10 | WBS 7 |
| S. Carolina | Y. Ilieva | Assoc Prof. | 0.10 | WBS 7 |
| Hampton | M. Kohl | Assoc. Prof. | 0.20 | WBS 8 manager |
| Hebrew U. | G. Ron | Asst. Prof. | 0.35 | Spokesperson, WBS 2,4 Manager |
| Tel Aviv | E. Piasetzky | Professor | 0.15 | WBS 2 |
| Tel Aviv | J. Lichtenstadt | Professor | 0.15 | WBS2 |

| WBS | Title | Scope | M&S | Labor | F&A | Contingency | Total w/o Contingency | Total with Contingency | Risk evaluation |
|-----|---------------------|---|-------------|-------------|-----------|-------------|-----------------------|------------------------|--|
| 1 | Frames | Will build support table and support frames for detectors. The support table will hold the detectors. Support frames will be constructed for the scintillators, veto detector, and beam monitor. Must be delivered in time for 2015 test run. | \$18,205 | \$24,550 | \$11,971 | \$12,587 | \$54,726 | \$67,313 | This WBS has minimal risk from cost, schedule, or technical objectives. |
| 2 | Scintillating Fiber | Construct scintillating fiber detector. Must be delivered for 2015 test run. | \$69,442 | \$70,000 | \$17,505 | \$29,115 | \$156,947 | \$186,062 | Minimal risk |
| 3 | Cerenkov | Construct two sapphire Cerenkov counters. Must be delivered for 2015 test run. | \$205,494 | \$4,000 | \$3,094 | \$27,115 | \$212,588 | \$239,703 | Minimal risk |
| 4 | Straw Chambers | Will build 4 straw tube chambers, with approximately 3000 straws and 15% spares. One chamber to be delivered by 2015 test run. | \$426,875 | \$161,436 | \$40,282 | \$160,105 | \$628,593 | \$788,698 | Schedule risk due to uncertain construction time |
| 5 | Cryo-target | Build 4 cm long liquid hydrogen target. Must be delivered for full run in 2016 | \$217,000 | \$386,428 | \$271,633 | \$208,193 | \$875,061 | \$1,083,254 | Minimal risk |
| 6 | Electronics &DAQ | Will order and test electronics and DAQ system. Half must delivered for 2015 test run. Write analysis software adequate for initial checking of system in first year, adequate for full run in second year. | \$413,519 | \$165,996 | \$86,317 | \$86,564 | \$665,832 | \$752,396 | Primary risk is in DAQ speed, which could lead to longer running times or poorer statistics than planned |
| 7 | Scintillator | Construct two time of flight plastic scintillator walls plus veto detector. Half of TOF, plus beam be delivered for 2015 test run | \$331,685 | \$89,335 | \$21,140 | \$87,687 | \$442,160 | \$529,847 | Minimal risk |
| 8 | GEM | Maintain current GEM detectors. Improve speed to specs. | \$28,434 | \$2,000 | \$1,680 | \$5,174 | \$32,114 | \$37,288 | Primary risk is in readout speed, which could lead to longer running times or poorer statistics than planned |
| 9 | Installation | Coordination of installation. | | \$414,000 | \$107,640 | \$129,838 | \$521,640 | \$552,938 | Minimal risk |
| | | | \$1,710,654 | \$1,317,745 | \$561,262 | \$647,838 | \$3,589,661 | \$4,237,500 | |

[illegible]

| Travel summary by institution | # of people staying for 1 week | # of people staying for 2 weeks | # of person-months for trips > 1 month | PD housing | Total | F&A | Total |
|-------------------------------|--------------------------------|---------------------------------|--|------------|----------|----------|-----------|
| | week | 2 week | month | | | | |
| GWU - Briscoe | | | | | | | |
| June 14 | 1 | 2 | | | \$9,950 | \$5,174 | \$15,124 |
| Dec 14 | 2 | 1 | | | \$8,800 | \$4,576 | \$13,376 |
| Jan 15 Collab | 3 | | | | \$7,650 | \$3,978 | \$11,628 |
| Year 1 Total | | | | | \$26,400 | \$13,728 | \$40,128 |
| Nov 15 | 4 | 0 | | | \$10,200 | \$5,304 | \$15,504 |
| Jan 16 Collab | 2 | 0 | | | \$5,100 | \$2,652 | \$7,752 |
| June 16 | 0 | | 2 | | \$10,700 | \$5,564 | \$16,264 |
| Year 2 Total | | | | | \$26,000 | \$13,520 | \$39,520 |
| Shifts | 0 | 8 | | | \$29,600 | \$15,392 | \$44,992 |
| Jan 17 Collab | 2 | 0 | | | \$5,100 | \$2,652 | \$7,752 |
| GS | 0 | | 4 | | \$21,400 | \$11,128 | \$32,528 |
| Year 3 Total | | | | | \$56,100 | \$29,172 | \$85,272 |
| Shifts | 0 | 8 | | | \$29,600 | \$15,392 | \$44,992 |
| Jan 18 Collab | 2 | 0 | | | \$5,100 | \$2,652 | \$7,752 |
| GS | 0 | | 4 | | \$21,400 | \$11,128 | \$32,528 |
| Year 4 Total | | | | | \$56,100 | \$29,172 | \$85,272 |
| GWU - Downie | | | | | | | |
| June 14 | 0 | 2 | | | \$7,400 | \$3,848 | \$11,248 |
| Dec 14 | 0 | 2 | 1 | | \$12,750 | \$6,630 | \$19,380 |
| Jan 15 Collab | 3 | | | | \$7,650 | \$3,978 | \$11,628 |
| spring install | | 4 | 2 | | \$25,500 | \$13,260 | \$38,760 |
| summer test | | | 4 | | \$21,400 | \$11,128 | \$32,528 |
| Year 1 Total | | | | | \$74,700 | \$38,844 | \$113,544 |
| Nov 15 | 0 | 4 | 2 | | \$25,500 | \$13,260 | \$38,760 |
| Jan 16 Collab | 3 | 0 | | | \$7,650 | \$3,978 | \$11,628 |
| winter install | 0 | 4 | 2 | | \$25,500 | \$13,260 | \$38,760 |
| spring test | | 3 | | | \$11,100 | \$5,772 | \$16,872 |
| summer work | | 6 | | | \$22,200 | \$11,544 | \$33,744 |
| Year 2 Total | | | | | \$91,950 | \$47,814 | \$139,764 |
| Shifts | 0 | 8 | | | \$29,600 | \$15,392 | \$44,992 |
| Jan 18 Collab | 3 | 0 | | | \$7,650 | \$3,978 | \$11,628 |
| Shifts/checkout | | 3 | | | \$11,100 | \$5,772 | \$16,872 |
| PD | 0 | | 3 | | \$16,050 | \$8,346 | \$24,396 |
| Year 3 Total | | | | | \$64,400 | \$33,488 | \$97,888 |
| Shifts | 0 | 8 | | | \$29,600 | \$15,392 | \$44,992 |
| Jan 18 Collab | 3 | 0 | | | \$7,650 | \$3,978 | \$11,628 |
| PD | 0 | | 3 | | \$16,050 | \$8,346 | \$24,396 |
| Year 4 Total | | | | | \$53,300 | \$27,716 | \$81,016 |
| Hampton | | | | | | | |
| June 14 | 0 | 2 | | | \$7,400 | \$3,552 | \$10,952 |
| Dec 14 | 0 | 2 | | | \$7,400 | \$3,552 | \$10,952 |
| Jan 15 Collab | 2 | | | | \$5,100 | \$2,448 | \$7,548 |
| Year 1 Total | | | | | \$19,900 | \$9,552 | \$29,452 |
| Aug 15 -PI, PD | 0 | 0 | 3 | | \$16,050 | \$7,704 | \$23,754 |
| Aug 15 -Student | | | 2 | | \$10,700 | \$0 | \$10,700 |
| Nov 15 | 0 | 0 | 3 | | \$16,050 | \$7,704 | \$23,754 |
| Nov 15 -Student | | | 1 | | \$5,350 | \$0 | \$5,350 |
| Jan 16 Collab | 2 | 0 | | | \$5,100 | \$2,448 | \$7,548 |
| Jan 16 Collab-student | 1 | 0 | | | \$2,550 | \$0 | \$2,550 |
| Year 2 Total | | | | | \$55,800 | \$17,856 | \$73,656 |
| Shifts -PI, PD | 0 | 2 | 4 | | \$28,800 | \$13,824 | \$42,624 |
| Shifts-student | | | 4 | | \$21,400 | \$0 | \$21,400 |
| Jan 17 Collab | 2 | 0 | | | \$5,100 | \$2,448 | \$7,548 |
| Jan 17 Collab-student | 1 | 0 | | | \$2,550 | \$0 | \$2,550 |

| | | | | | | |
|-----------------------|---|---|---|----------|----------|----------|
| Year 3 Total | | | | \$57,850 | \$16,272 | \$74,122 |
| Shifts -PI, PD | 0 | 2 | 4 | \$28,800 | \$13,824 | \$42,624 |
| Shifts-student | | | 4 | \$21,400 | \$0 | \$21,400 |
| Jan 18 Collab | 2 | 0 | | \$5,100 | \$2,448 | \$7,548 |
| Jan 18 Collab-student | 1 | 0 | | \$2,550 | \$0 | \$2,550 |
| Year 4 Total | | | | \$57,850 | \$16,272 | \$74,122 |

Hebrew Univ.

| | | | | | | |
|----------------|--|--|---|------------|--------|------------|
| GS straw setup | | | 1 | \$5,800.00 | \$0.00 | \$5,800.00 |
| Year 1 Total | | | | \$5,800.00 | \$0.00 | \$5,800.00 |
| GS straw setup | | | 1 | \$5,800.00 | \$0.00 | \$5,800.00 |
| Year 2 Total | | | | \$5,800.00 | \$0.00 | \$5,800.00 |

Rutgers

| | | | | | | |
|----------------|---|---|----------|----------|----------|-----------|
| Jun 14 | | 2 | | \$7,400 | \$2,072 | \$9,472 |
| Dec 14 | | 2 | | \$7,400 | \$2,072 | \$9,472 |
| Jan 15 Collab | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD housing | | | \$12,000 | \$12,000 | \$6,720 | \$18,720 |
| Year 1 Total | | | | \$37,000 | \$13,720 | \$50,720 |
| June/July 15 | | 4 | | \$14,800 | \$4,144 | \$18,944 |
| Dec 15 | | 4 | | \$14,800 | \$4,144 | \$18,944 |
| Jan 16 Collab | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| May /June 16 | | 4 | | \$14,800 | \$4,144 | \$18,944 |
| PD | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD housing | | | \$12,000 | \$12,000 | \$6,720 | \$18,720 |
| Year 2 Total | | | | \$66,600 | \$22,008 | \$88,608 |
| Shifts | | 8 | | \$29,600 | \$8,288 | \$37,888 |
| Jan 17 Collab | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| May /June 17 | | 2 | | \$7,400 | \$2,072 | \$9,472 |
| PD | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD housing | | | \$12,000 | \$12,000 | \$6,720 | \$18,720 |
| Expert housing | | | 4 | \$21,400 | \$5,992 | \$27,392 |
| Year 3 Total | | | | \$80,600 | \$25,928 | \$106,528 |
| Shifts | | 8 | | \$29,600 | \$8,288 | \$37,888 |
| Jan 18 Collab | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD | 2 | | | \$5,100 | \$1,428 | \$6,528 |
| PD housing | | | \$12,000 | \$12,000 | \$6,720 | \$18,720 |
| Expert housing | | | 4 | \$21,400 | \$5,992 | \$27,392 |
| Year 4 Total | | | | \$73,200 | \$23,856 | \$97,056 |

South Carolina

| | | | | | | |
|---------------|---|---|---|----------|----------|----------|
| Jan 15 Collab | 1 | | | \$2,460 | \$812 | \$3,272 |
| Year 1 Total | | | | \$2,460 | \$812 | \$3,272 |
| Jan 16 Collab | 1 | | | \$2,460 | \$812 | \$3,272 |
| Installation | | | 2 | \$13,120 | \$4,330 | \$17,450 |
| Year 2 total | | | | \$15,580 | \$5,141 | \$20,721 |
| Jan 17 Collab | 1 | | | \$2,460 | \$812 | \$3,272 |
| GS on site | | | 2 | \$13,120 | \$4,330 | \$17,450 |
| Shifts | | 7 | | \$26,880 | \$8,870 | \$35,750 |
| Year 3 total | | | | \$42,460 | \$14,012 | \$56,472 |
| Jan 18 Collab | 1 | | | \$2,460 | \$812 | \$3,272 |
| GS on site | | | 2 | \$13,120 | \$4,330 | \$17,450 |
| Shifts | | 7 | | \$26,880 | \$8,870 | \$35,750 |
| Year 4 total | | | | \$42,460 | \$14,012 | \$56,472 |

Tel Aviv

| | | | | | | |
|-----------------|--|---|--|---------|-------|---------|
| GS Sci Fi setup | | 1 | | \$6,400 | \$960 | \$7,360 |
| Year 2 Total | | | | \$6,400 | \$960 | \$7,360 |

Temple

| | | | | | | |
|--------------|--|--|---|----------|---------|----------|
| GS at HU | | | | \$25,200 | \$6,552 | \$31,752 |
| Year 1 Total | | | | \$25,200 | \$6,552 | \$31,752 |
| GS | | | 2 | \$10,700 | \$2,782 | \$13,482 |
| Year 2 Total | | | | \$10,700 | \$2,782 | \$13,482 |

| # | Info | WBS-Code | Title | Giv. Plan. Dur. | ID | Flag | # Predecessors | Actual Start | Exp. Duration | Expected Start | Expected End | Milestone | Resources | % ...pl. | Q3 / 2013 | Q4 / 2013 | Q1 / 2014 | Q2 / 2014 | Q3 / 2014 | Q4 / 2014 | Q1 / 2015 | Q2 / 2015 | Q3 / 2015 | Q4 / 2015 | Q1 / 2016 | Q2 / 2016 | Q3 / 2016 |
|----|---------|----------|--------------------------------|-----------------|-----|------|----------------|--------------|---------------|----------------|--------------|-----------|-----------|----------|-----------|-----------|----------------------------|--------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| 0 | ☰ | | MUSE | | 128 | | | | 2.7 years | 2/3/14 | 7/27/16 | | | 0% | | | MUSE | | | | | | | | | | |
| 1 | 1 | | Frames & Design | | 7 | | | | 1.87 years | 3/1/14 | 11/18/15 | | | 0% | | | Frames & Design | | | | | | | | | | |
| 2 | 1.1 | | Table | | 36 | | | | 1.12 years | 3/1/14 | 3/13/15 | | | 0% | | | Table | | | | | | | | | | |
| 3 | 1.1.1 | | Design table | 9 months | 47 | | | 3/1/14 | 9 months | 3/1/14 | 11/7/14 | ☐ | | 0% | | | Design table | 9 months | | | | | | | | | |
| 4 | 1.1.2 | | Buy table parts | | 125 | | 3; 135 | | 1 month | 11/10/14 | 12/5/14 | | | 0% | | | | | | | | | | | | | |
| 5 | 1.1.2.1 | | rotary bearings | 1 month | 92 | | | | 1 month | 11/10/14 | 12/5/14 | ☐ | | 0% | | | | Buy table parts | | | | | | | | | |
| 6 | 1.1.2.2 | | extrusions for frame | 1 month | 4 | | | | 1 month | 11/10/14 | 12/5/14 | ☐ | | 0% | | | | rotary bearings | 1m | | | | | | | | |
| 7 | 1.1.2.3 | | linear bearings | 1 month | 67 | | | | 1 month | 11/10/14 | 12/5/14 | ☐ | | 0% | | | | extrusions for frame | 1m | | | | | | | | |
| 8 | 1.1.3 | | Machine & assemble table | | 74 | | 4 | | 1.5 months | 12/8/14 | 1/16/15 | | | 0% | | | | linear bearings | 1m | | | | | | | | |
| 9 | 1.1.3.1 | | machine donuts and table | 1 month | 30 | | | | 1 month | 12/8/14 | 1/2/15 | ☐ | | 0% | | | | Machine & assemble table | | | | | | | | | |
| 10 | 1.1.3.2 | | machine extrusions | 1 month | 98 | | | | 1 month | 12/8/14 | 1/2/15 | ☐ | | 0% | | | | machine donuts and table | 1m | | | | | | | | |
| 11 | 1.1.3.3 | | assemble table | 2 weeks | 91 | | 9; 10 | | 2 weeks | 1/5/15 | 1/16/15 | ☐ | | 0% | | | | machine extrusions | 1m | | | | | | | | |
| 12 | 1.1.4 | | Ship and assemble table | | 60 | | | | 2 months | 1/19/15 | 3/13/15 | | | 0% | | | | assemble table | 2 | | | | | | | | |
| 13 | 1.1.4.1 | | Ship to PSI | 1 month | 113 | | 8 | | 1 month | 1/19/15 | 2/13/15 | ☐ | | 0% | | | | Ship and assemble table | | | | | | | | | |
| 14 | 1.1.4.2 | | Assemble table at PSI | 1 month | 1 | | 13 | | 1 month | 2/16/15 | 3/13/15 | ☐ | | 0% | | | | Ship to PSI | 1m | | | | | | | | |
| 15 | 1.2 | | Table ready at PSI | | 86 | | 14 | | 0 hours | 3/13/15 | 3/13/15 | ☑ | | 0% | | | | Assemble table at PSI | 1m | | | | | | | | |
| 16 | 1.3 | | Scintillator and Veto | | 48 | | | | 1.42 years | 7/1/14 | 10/21/15 | | | 0% | | | Scintillator and Veto | | | | | | | | | | |
| 17 | 1.3.1 | | Design scintillator frames | 6 months | 96 | | | 7/1/14 | 6 months | 7/1/14 | 12/15/14 | ☐ | | 0% | | | Design scintillator frames | 6 months | | | | | | | | | |
| 18 | 1.3.2 | | Build first scintillator frame | 2 months | 66 | | 17; 135 | | 2 months | 12/16/14 | 2/9/15 | ☐ | | 0% | | | | Build first scintillator frame | 2m | | | | | | | | |
| 19 | 1.3.3 | | Ship first frames to PSI | 1 month | 54 | | 18 | | 1 month | 2/10/15 | 3/9/15 | ☐ | | 0% | | | | Ship first frames to PSI | 1m | | | | | | | | |
| 20 | 1.3.4 | | Build second scint. frames | 2 months | 38 | | 18; 136 | | 2 months | 7/2/15 | 8/26/15 | ☐ | | 0% | | | | Build second scint. frames | 2m | | | | | | | | |
| 21 | 1.3.5 | | Ship second set to PSI | 1 month | 120 | | 20 | | 1 month | 8/27/15 | 9/23/15 | ☐ | | 0% | | | | Ship second set to PSI | 1m | | | | | | | | |
| 22 | 1.3.6 | | Assemble at PSI | 1 month | 80 | | 21 | | 1 month | 9/24/15 | 10/21/15 | ☐ | | 0% | | | | Assemble at PSI | 1m | | | | | | | | |
| 23 | 1.3.7 | | Veto design | 2 months | 8 | | 17 | | 2 months | 12/16/14 | 2/9/15 | ☐ | | 0% | | | | Veto design | 2m | | | | | | | | |
| 24 | 1.3.8 | | Build veto | 1 month | 103 | | 23 | | 1 month | 2/10/15 | 3/9/15 | ☐ | | 0% | | | | Build veto | 1m | | | | | | | | |
| 25 | 1.3.9 | | Ship veto to PSI | 1 month | 14 | | 24 | | 1 month | 3/10/15 | 4/6/15 | ☐ | | 0% | | | | Ship veto to PSI | 1m | | | | | | | | |
| 26 | 1.4 | | Beam Monitor | | 68 | | | | 5 months | 7/2/15 | 11/18/15 | | | 0% | | | | Beam Monitor | | | | | | | | | |
| 27 | 1.4.1 | | Design beam monitor | 2 months | 61 | | 23; 136 | | 2 months | 7/2/15 | 8/26/15 | ☐ | | 0% | | | | Design beam monitor | 2m | | | | | | | | |
| 28 | 1.4.2 | | Build beam monitor | 1 month | 15 | | 27 | | 1 month | 8/27/15 | 9/23/15 | ☐ | | 0% | | | | Build beam monitor | 1m | | | | | | | | |
| 29 | 1.4.3 | | Ship to PSI | 1 month | 122 | | 28 | | 1 month | 9/24/15 | 10/21/15 | ☐ | | 0% | | | | Ship to PSI | 1m | | | | | | | | |
| 30 | 1.4.4 | | Assemble PSI | 1 month | 42 | | 29 | | 1 month | 10/22/15 | 11/18/15 | ☐ | | 0% | | | | Assemble PSI | 1m | | | | | | | | |
| 31 | 2 | | Scintillating Fiber | | 40 | | | | 1.21 years | 7/2/14 | 8/11/15 | | | 0% | | | Scintillating Fiber | | | | | | | | | | |
| 32 | 2.1 | | Order Materials | | 99 | | 135 | | 6 months | 7/2/14 | 12/16/14 | | | 0% | | | Order Materials | | | | | | | | | | |
| 33 | 2.1.1 | | Order Fiber | 6 months | 64 | | | | 6 months | 7/2/14 | 12/16/14 | ☐ | | 0% | | | | Order Fiber | 6 months | | | | | | | | |
| 34 | 2.1.2 | | Order PMTs | 6 months | 53 | | | | 6 months | 7/2/14 | 12/16/14 | ☐ | | 0% | | | | Order PMTs | 6 months | | | | | | | | |
| 35 | 2.1.3 | | Order tools | 2 months | 107 | | | | 2 months | 7/2/14 | 8/26/14 | ☐ | | 0% | | | | Order tools | 2m | | | | | | | | |
| 36 | 2.2 | | Prototype | 1 month | 112 | | 32 | | 1 month | 12/17/14 | 1/13/15 | ☐ | | 0% | | | | Prototype | 1m | | | | | | | | |
| 37 | 2.3 | | Construct fibers | 3 months | 16 | | 36 | | 3 months | 1/14/15 | 4/7/15 | ☐ | | 0% | | | | Construct fibers | 3 months | | | | | | | | |
| 38 | 2.4 | | Mount fibers | 1 month | 43 | | 37 | | 1 month | 4/8/15 | 5/5/15 | ☐ | | 0% | | | | Mount fibers | 1m | | | | | | | | |
| 39 | 2.5 | | Testing | 1 month | 76 | | 38 | | 1 month | 5/6/15 | 6/2/15 | ☐ | | 0% | | | | Testing | 1m | | | | | | | | |
| 40 | 2.6 | | Ship to PSI | 2 weeks | 20 | | 39 | | 2 weeks | 6/3/15 | 6/16/15 | ☐ | | 0% | | | | Ship to PSI | 2 | | | | | | | | |
| 41 | 2.7 | | Test at PSI | 2 months | 59 | | 40 | | 2 months | 6/17/15 | 8/11/15 | ☐ | | 0% | | | | Test at PSI | 2m | | | | | | | | |
| 42 | 3 | | Cerenkov | | 105 | | | | 1.87 years | 2/3/14 | 10/21/15 | | | 0% | | | Cerenkov | | | | | | | | | | |
| 43 | 3.1 | | Design Cerenkov | 5 months | 85 | | | | 5 months | 2/3/14 | 6/20/14 | ☐ | | 0% | | | Design Cerenkov | 5 months | | | | | | | | | |
| 44 | 3.2 | | Buy materials first part | | 77 | | 135 | | 4 months | 7/2/14 | 10/21/14 | | | 0% | | | | Buy materials first part | | | | | | | | | |
| 45 | 3.2.1 | | Buy first 4 tubes | 4 months | 109 | | | | 4 months | 7/2/14 | 10/21/14 | ☐ | | 0% | | | | Buy first 4 tubes | 4 months | | | | | | | | |
| 46 | 3.2.2 | | Buy sapphire | 3 months | 73 | | | | 3 months | 7/2/14 | 9/23/14 | ☐ | | 0% | | | | Buy sapphire | 3 months | | | | | | | | |
| 47 | 3.2.3 | | Buy assembly materials | 1 month | 45 | | | | 1 month | 7/2/14 | 7/29/14 | ☐ | | 0% | | | | Buy assembly materials | 1m | | | | | | | | |
| 48 | 3.3 | | Assemble | 2 months | 33 | | 44 | | 2 months | 10/22/14 | 12/16/14 | ☐ | | 0% | | | | Assemble | 2m | | | | | | | | |
| 49 | 3.4 | | Ship to PSI | 1 month | 13 | | 48 | | 1 month | 12/17/14 | 1/13/15 | ☐ | | 0% | | | | Ship to PSI | 1m | | | | | | | | |
| 50 | 3.5 | | First set at PSI | | 51 | | 49 | | 0 hours | 1/13/15 | 1/13/15 | ☑ | | 0% | | | | First set at PSI | | | | | | | | | |
| 51 | 3.6 | | Buy 5 tubes | 4 months | 9 | | 136 | | 4 months | 7/2/15 | 10/21/15 | ☐ | | 0% | | | | Buy 5 tubes | 4 months | | | | | | | | |
| 52 | 3.7 | | Buy mounting fixtures | 1 month | 34 | | 136 | | 1 month | 7/2/15 | 7/29/15 | ☐ | | 0% | | | | Buy mounting fixtures | 1m | | | | | | | | |
| 53 | 3.8 | | Frame for 2nd cerenkov | 2 months | 71 | | 52 | | 2 months | 7/30/15 | 9/23/15 | ☐ | | 0% | | | | Frame for 2nd cerenkov | 2m | | | | | | | | |
| 54 | 3.9 | | Install at PSI | 1 month | 90 | | 53 | | 1 month | 9/24/15 | 10/21/15 | ☐ | | 0% | | | | Install at PSI | 1m | | | | | | | | |
| 55 | 4 | | Straw Chambers | | 87 | | 135 | | 1.83 years | 7/2/14 | 3/8/16 | | | 0% | | | Straw Chambers | | | | | | | | | | |
| 56 | 4.1 | | Order straw material | 6 months | 11 | | | | 6 months | 7/2/14 | 12/16/14 | ☐ | | 0% | | | | Order straw material | 6 months | | | | | | | | |
| 57 | 4.2 | | Order gas system | 2 months | 118 | | | | 2 months | 7/2/14 | 8/26/14 | ☐ | | 0% | | | | Order gas system | 2m | | | | | | | | |
| 58 | 4.3 | | Set up clean room | 2 months | 57 | | 135 | | 2 months | 7/2/14 | 8/26/14 | ☐ | | 0% | | | | Set up clean room | 2m | | | | | | | | |
| 59 | 4.4 | | Manufacture jigs | 2 months | 111 | | 135 | | 2 months | 7/2/14 | 8/26/14 | ☐ | | 0% | | | | Manufacture jigs | 2m | | | | | | | | |
| 60 | 4.5 | | Design chamber mounting | 2 months | 127 | | 135 | | 2 months | 7/2/14 | 8/26/14 | ☐ | | 0% | | | | Design chamber mounting | 2m | | | | | | | | |
| 61 | 4.6 | | manufacture straws ch 1 | 2 months | 75 | | 56; 58; 59 | | 2 months | 12/17/14 | 2/10/15 | ☐ | | 0% | | | | manufacture straws ch 1 | 2m | | | | | | | | |
| 62 | 4.7 | | manufacture gas dist. | 2 months | 95 | | 57 | | 2 months | 8/27/14 | 10/21/14 | ☐ | | 0% | | | | manufacture gas dist. | 2m | | | | | | | | |
| 63 | 4.8 | | machine chamber mounting | 2 months | 6 | | 60 | | 2 months | 8/27/14 | 10/21/14 | ☐ | | 0% | | | | machine chamber mounting | 2m | | | | | | | | |
| 64 | 4.9 | | assemble & test ch 1 | 2 months | 65 | | 61; 63 | | 2 months | 2/11/15 | 4/7/15 | ☐ | | 0% | | | | assemble & test ch 1 | 2m | | | | | | | | |
| 65 | 4.10 | | ship to PSI | 1 month | 69 | | 64 | | 1 month | 4/8/15 | 5/5/15 | ☐ | | 0% | | | | ship to PSI | 1m | | | | | | | | |
| 66 | 4.11 | | Commission ch 1 at PSI | 1 month | 97 | | 65 | | 1 month | 5/6/15 | 6/2/15 | ☐ | | 0% | | | | Commission ch 1 at PSI | 1m | | | | | | | | |
| 67 | 4.12 | | Ch 1 ready at PSI | | 19 | | 66 | | 0 hours | 6/2/15 | 6/2/15 | ☑ | | 0% | | | | Ch 1 ready at PSI | | | | | | | | | |
| 68 | 4.13 | | Purchase 2nd gas system | 1 month | 21 | | 61 | | 1 month | 2/11/15 | 3/10/15 | ☐ | | 0% | | | | Purchase 2nd gas system | 1m | | | | | | | | |
| 69 | 4.14 | | Build ch 2-4 | 9 months | 119 | | 64 | | 9 months | 4/8/15 | 12/15/15 | ☐ | | 0% | | | | Build ch 2-4 | 9 months | | | | | | | | |
| 70 | 4.15 | | Ship ch 2-4 to psi | 1 month | 2 | | 69 | | 1 month | 12/16/15 | 1/12/16 | ☐ | | 0% | | | | Ship ch 2-4 to psi | 1m | | | | | | | | |
| 71 | 4.16 | | Commission at PSI | 2 months | 79 | | 70 | | 2 months | 1/13/16 | 3/8/16 | ☐ | | 0% | | | | Commission at PSI | 2m | | | | | | | | |
| 72 | 5 | | Cryo-target | | 37 | | | | | | | | | | | | | | | | | | | | | | |

Summary of Basis of Estimates and Risk Assessment

WBS-1 Detector Frames and Support Table

The items in WBS 1 are straight-forward frames and holders. Designs are still in a preliminary stage. The estimates are based on past experience and discussions with machine shop. The total cost is a small, so even with a substantial uncertainty the cost-risk is small. The schedule and technical risks are minimal.

WBS-2 SciFi Detector

Scintillating fiber technology is well established. The primary costs are the fibers and phototubes. Costs are based on recent quotes. The labor estimate is based on past experience. There is low technical, cost, or schedule risk.

WBS-3 Beam Cerenkov Detectors

The major cost for the Cerenkov detector is for the phototubes. The PMT cost estimate is based on a recent quote. There is little schedule, technical, or cost risk.

WBS-4 Straw Tube Tracker

The straw tube chambers are based on standard technology, using the design and techniques developed for the PANDA detector. Cost estimates are primarily based on the PANDA experience, and recent quotes for the straws. There is relatively little cost or technical risk. Straw construction is labor intensive and there is some uncertainty on the time for construction. The primary risk is to the schedule.

WBS 5 – Cryo Target

The cryo-target is based on well established and tested technology. The costs for materials and labor are based on recent experience with similar targets. The technical, cost, and schedule risks are small.

WBS 6 – Electronics/DAQ/Analysis

The primary cost in this WBS is for electronics are off-the-shelf items. Recent quotes are available for most items. The other cost is for tuning the software to enable data acquisition at the highest rates desired. The cost and technical risks are small. There is moderate risk to the schedule based on the uncertainty achieving the highest rates.

WBS 7 – Scintillator

The scintillator detectors are based on proven technology. The primary cost is for materials and are all based on recent quotes. The cost, schedule and technical risks are small.

WBS-8 GEM

The GEM detectors already exist. The major issue is achieving the desired data acquisition rate.

| WBS | WBS | Item | Risk | Probability | Impact | | | |
|-----|----------|----------------------------|---|-------------|--------|------|-------|---------|
| | sub item | | | | Cost | Time | Scope | Quality |
| 1 | 1.1 | Support Table | Design is preliminary, cost increase, added design time | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| | 1.3 | Scintillator frame | Design is preliminary, cost increase, added design time | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| | 1.4 | Beam monitor frame | Design is preliminary, cost increase, added design time | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| 2 | 2.1.1 | Order fiber | cost increase | 0.3 | 0.2 | 0.05 | 0.05 | 0.05 |
| | 2.1.2 | Order PMT | cost increase | 0.3 | 0.2 | 0.05 | 0.05 | 0.05 |
| | | | Doesn't meet efficiency or timing specs. | 0.3 | 0.2 | 0.05 | 0.1 | 0.1 |
| 3 | 3.3 | Cerenkov | Doesn't meet specs | 0.2 | 0.2 | 0.1 | 0.05 | 0.1 |
| 4 | 4.1 | Order materials | cost increase | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| | 4.5 | Chamber mount | cost increase | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| | 4.9 | Chamber 1 | takes too long to build | 0.3 | 0.2 | 0.2 | 0.05 | 0.05 |
| | 4.14 | Chamber 2-4 | takes too long to build | 0.3 | 0.2 | 0.2 | 0.05 | 0.05 |
| 5 | 5.3 | Order major elements | cost increase | 0.3 | 0.2 | 0.05 | 0.05 | 0.05 |
| | 5.4 | Construct prototype | Unable to find qualified tech | 0.2 | 0.4 | 0.2 | 0.05 | 0.05 |
| | 5.5 | test of prototype | failure of prototype | 0.3 | 0.2 | 0.4 | 0.05 | 0.05 |
| | 5.11 | test complete system | failure of system | 0.1 | 0.2 | 0.2 | 0.05 | 0.05 |
| 6 | 6.1 | Order electronics | cost increase | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| | 6.4 | Develop DAQ | extra time to develop DAQ | 0.3 | 0.4 | 0.4 | 0.1 | 0.05 |
| | 6.7 | Order 2nd half electronics | cost increase | 0.3 | 0.2 | 0.1 | 0.05 | 0.05 |
| 7 | 7.2 | Materials for Scintillator | cost increase | 0.3 | 0.2 | 0.05 | 0.05 | 0.05 |
| | 7.3 | Construction | takes longer than expected | 0.3 | 0.2 | 0.05 | 0.05 | 0.05 |
| 8 | 8.1 | Order electronics | cost increase | 0.3 | 0.2 | 0.2 | 0.05 | 0.05 |
| | 8.4 | Test system | unable to get speed needed | 0.5 | 0.4 | 0.4 | 0.2 | 0.2 |

Remedy

Summary of WBS requirements and quality control.

WBS-1 Detector Frames and Support Table

Requirements:

Rotary stage position reproducible to about 0.5 mil or 10 μm ,
corresponding to angular repeatability of < 0.1 mr.

Translation stage movement distance known to 1 mm, with angle
changes less than 0.1 mr horizontal x 1 mr vertical.

Supports detectors.

Quality Control:

Careful mechanical construction

Survey

laser pointing

WBS-2 SciFi Detector

Requirements:

Timing resolution better then 1ns per fiber (becomes better than ~700ps when demanding 2 planes).

Position resolution – Fiber size 2mm.

Efficiency better then 95%/plane (better than 99% when demanding 2/3 planes).

Quality Control:

Resolution and timing:

Cosmics tests at TAU.

Beam tests at PSI.

Efficiency:

Cosmics tests at TAU.

Online testing at PSI.

WBS-3 Beam Cerenkov Detectors

Requirements:

Timing resolution better than 0.1 ns.

Efficiency about 99% or better for muons.

Quality Control:

Timing resolution:

Cosmic and beam tests at PSI, with respect to fast scintillator.

Vary angle of Cerenkov wrt beam.

Efficiency:

Beam testing at PSI, with tracking or scintillator stack.

WBS-4 Straw Tube Tracker

Requirements:

- 150 um position resolution on hit straws (giving a 1mr angular resolution with 2 chambers).
- At least 95% efficiency (giving better than 99.999% efficiency for 3 out of 5).
- Time resolution not critical.
- Position repeatability of the chamber to within 10 um

Quality Control

Resolution:

- Test individual straws with a radioactive source.
- Test multiple planes with source.
- Test chambers at PSI with GEM tracking.

Efficiency:

- Test straws/planes with cosmics.
- Online testing at PSI.

Repeatability:

- Tests at PSI with GEMs/Frames.

WBS 5 – Cryo Target

Requirements

Cylindrical liquid hydrogen target with length of 4 cm and diameter of 4 cm.

WBS 6 – Electronics/DAQ/Analysis

Requirements

3 KHz data acquisition rate.

WBS 7 – Scintillator

Requirements:

- Average detection efficiency $\varepsilon > 0.95$.
- Average time resolution, $\sigma < 70$ ps.

Quality Control

- BC-404 Scintillators are inspected for damages, inclusions, and refraction index inhomogeneities
- Hamamatsu R9779 PMTs are tested for signal integrity, signal-to-noise ratio, gain, HV requirements, and magnetic field shielding
- Counter Pre-Check: Counters are inspected for void-free glued PMT-to-scintillator transition and light tightness, set to final gain-balanced HVs
- Counter Full-Check: With Three-Bar-Method position dependent and overall time resolutions, effective speed of light, left and right attenuation lengths (BAL and TAL) are programmatically analyzed and automatically stored
- Database: All acquired information is stored and retraceable

WBS-8 GEM

Requirements:

1. <100 um position resolution (giving better than 1mr angular resolution with 3 GEMs). Achieved 75 um at OLYMPUS.
2. At least 95% efficiency (has been established with OLYMPUS, investigations are ongoing). Can use any-2-of-3 to define track for higher efficiency.
3. No time information; GEMs require external trigger
4. GEM track to provide reference direction for scattering angle measurement
5. Readout speed of 2 kHz at 20% deadtime, corresponding to 200 usec readout time per event

Steps to achieve fast readout:

Currently 400 Hz readout rate has been established for two telescopes, where the readout time per event has been 1.8ms. A 200 us readout per event is needed to achieve 2 kHz at 20% deadtime.

One can gain a factor 2 by implementing block transfer of 32-bit words, and another factor 2 by using only one telescope, i.e. 500 usec. However, another factor 2.5 is needed.

With the existing system design, one can gain another factor 3 by using three VME crates with three CPUs and MPD FPGA boards, respectively, i.e. by adding another two. Hampton has one spare VME crate with CPU and MPD from OLYMPUS still available. Reading out with one VME crate per GEM will require a slight reconfiguration of the telescope cabling. The cost for this approach is included in this WBS.

Alternatively, it has been discussed to avoid the VME bus limitation by employing a UDP protocol via PCI bus. This option will be explored further but requires R&D and hence involves certain risks. It would be desirable to establish the required readout speed with the GEM telescope as soon as possible, therefore the funds are requested in the first year.

One telescope along with one MPD is now on its way from PSI back to Hampton, where one set of VME crate and CPU is available. The additional two sets of VME crate with CPU and MPD will be set up and tested at Hampton University in fall 2014 before the new electronics are shipped to PSI.

| WBS-Code | Title | M&S | Labor | F&A | Contingency | Total w/o Contingency | Total with Contingency | BOE Quotes and estimates based on prev. exp. |
|----------|--------------------------------|----------|----------|----------|-------------|--------------------------|---------------------------|--|
| 1 | Frames & Design | | | | | | | |
| 1.1 | Table | | | | | \$0 | \$0 | |
| 1.1.1 | Design table | | | | | \$0 | \$0 | |
| 1.1.2 | Buy table parts | | | | | \$0 | \$0 | |
| 1.1.2.1 | rotary bearings | \$3,355 | | \$939 | \$988 | \$4,294 | \$5,282 | |
| 1.1.2.2 | extrusions for fram | \$4,000 | | \$1,120 | \$1,178 | \$5,120 | \$6,298 | |
| 1.1.2.3 | linear bearings | \$2,100 | | \$588 | \$618 | \$2,688 | \$3,306 | |
| 1.1.3 | Machine & assemble table | | \$4,800 | \$1,344 | \$1,413 | \$6,144 | \$7,557 | |
| 1.1.3.1 | machine donuts and table | \$7,000 | | \$1,960 | \$2,061 | \$8,960 | \$11,021 | |
| 1.1.3.2 | machine extrusions | | | \$0 | \$0 | \$0 | \$0 | |
| 1.1.3.3 | assemble table | | | \$0 | \$0 | \$0 | \$0 | |
| 1.1.4 | Ship and assemble table | | \$8,000 | \$2,240 | \$2,355 | \$10,240 | \$12,595 | |
| 1.1.4.1 | Ship to PSI | | \$5,000 | \$1,400 | \$1,472 | \$6,400 | \$7,872 | |
| 1.1.4.2 | Assemble table at PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.2 | Table ready at PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3 | Scintillator and Veto | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.1 | Design scintillator frames | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.2 | Build first scintillator frame | \$1,500 | \$1,500 | \$840 | \$883 | \$3,840 | \$4,723 | |
| 1.3.3 | Ship first frames to PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.4 | Build second scint. frames | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.5 | Ship second set to PSI | | \$4,000 | \$1,120 | \$1,178 | \$5,120 | \$6,298 | |
| 1.3.6 | Assemble at PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.7 | Veto design | | | \$0 | \$0 | \$0 | \$0 | |
| 1.3.8 | Build veto | \$250 | \$250 | \$140 | \$147 | \$640 | \$787 | |
| 1.3.9 | Ship veto to PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.4 | Beam Monitor | | | \$0 | \$0 | \$0 | \$0 | |
| 1.4.1 | Design beam monitor | | | \$0 | \$0 | \$0 | \$0 | |
| 1.4.2 | Build beam monitor | | | \$0 | \$0 | \$0 | \$0 | |
| 1.4.3 | Ship to PSI | | | \$0 | \$0 | \$0 | \$0 | |
| 1.4.4 | Assemble PSI | | \$1,000 | \$280 | \$294 | \$1,280 | \$1,574 | |
| | total | \$18,205 | \$24,550 | \$11,971 | \$12,587 | \$54,726 | \$67,313 | |

| SciFi | start date | end date | M&S or Labor | Cost | F&A | Contingency | Total w/o contingency | BOE | | | |
|--|------------|-----------|--------------|-----------|----------|-------------|--------------------------|----------|--------------------------------|---------|--|
| 8 PMTs | | | | \$22,742 | \$0 | \$2,274 | \$22,742 | Quote | 292800 Yen/each | \$2,843 | Contingency based on 10% currency fluctuation |
| Send out orders for SciFi, WLS Fibers, PMTs | 31-Jul-14 | 27-Jan-15 | M&S | \$31,700 | \$4,755 | \$7,291 | \$36,455 | Estimate | | | 20% contingency |
| Design mounting structures | 31-Jul-14 | 29-Sep-14 | Labor | | | \$0 | \$0 | Estimate | | | |
| Order cutting/polishing tools | 31-Jul-14 | 29-Sep-14 | M&S | \$15,000 | \$2,250 | \$3,450 | \$17,250 | Quotes | | | 20% cotingency |
| | | | | | | | | | From non NSF/DOE Sources | | |
| Design Bases + Electronics | 31-Jul-14 | 29-Sep-14 | Both | | | | | E-Shop | | | |
| Prototype construction | 01-Feb-15 | 03-Mar-15 | Labor | | | | | | | | |
| Construct fibers | 01-Mar-15 | 30-May-15 | Labor | | | | | | | | |
| Machine frames | 01-Apr-15 | 01-May-15 | Labor | | | | | | | | |
| Mount Fibers | 01-Jun-15 | 01-Jul-15 | Labor | | | | | | | | |
| Commisioning tests at TAU | 01-Jul-15 | 31-Jul-15 | Labor | | | | | | | | |
| Shipping to PSI | 01-Aug-15 | 31-Aug-15 | Labor | | | | | | | | |
| Tests at PSI (Beam + Cosmics) | 01-Sep-15 | 31-Oct-15 | Labor | | | | | | | | |
| Total M&S | | | | \$69,442 | \$7,005 | \$13,015 | \$76,447 | | | | |
| Labor | | | | \$70,000 | \$10,500 | \$16,100 | \$80,500 | | | | |
| total | | | | \$139,442 | \$17,505 | \$29,115 | \$156,947 | | | | |
| Labor | | F&A | Contingency | 20% | | | | | | | |
| Technician year 1 | \$15,000 | \$2,250 | \$3,450 | | | | | | | | |
| year 2 | \$5,000 | \$750 | \$1,150 | | | | | | | | |
| GS year 1 | \$25,000 | \$3,750 | \$5,750 | | | | | | | | |
| GS year 2 | \$25,000 | \$3,750 | \$5,750 | | | | | | | | |
| | \$70,000 | \$10,500 | \$16,100 | | | | | | | | |

| WBS 3 | Beam Cerenkov part | start date | end date | M&S or Labor | M & S & E Cost | External Skilled Paid Labor | Employee / Student | BOE | Funding Source | Cost to Sponsor | Contingency | Reason for Contingency | F&A | Total Equipment only | Contingency equipment only |
|-------|---|-------------|--------------|-----------------------------------|----------------|-----------------------------|--------------------|--|----------------|-----------------|-------------|--|----------|----------------------|----------------------------|
| 3.1 | Design frame for 1st Cerenkov | 1-Apr-2014 | 1-Sep-2015 | Labor | \$0 | | | existing manpower | NSF/DOE | \$0 | | | | \$0 | |
| 3.2 | beam test of Photek, Photonis | 15-Jun-2014 | 30-Jun-2014 | travel - \$6,000 asked separately | | | | recent experience for 1 1-week + 1 2-week trips | NSF/DOE | \$0 | \$300 | recent experience for trip costs variations | | \$0 | |
| 3.2 | Order first 4 Photek MCP-PMT 240's | 1-Aug-2014 | 1-Dec-2014 | Equipment | \$87,600 | | | Photek quote, 1/24/2014 | NSF / DOE | \$87,600 | \$8,760 | 10% based on currency fluctuations | | \$87,600 | \$8,760 |
| 3.3 | Order sapphire bars | 1-Aug-2014 | 1-Nov-2014 | Equipment | \$5,050 | | | DeiMar Photonics quote, 2/6/14 | NSF / DOE | \$5,050 | \$505 | 10% based on currency fluctuations | \$1,414 | \$6,464 | \$505 |
| 3.4 | Order 5 mounting fixtures | 1-Sep-2014 | 1-Oct-2014 | Equipment | \$125 | | | purchase of 3d printed mounting fixture in October 2013 | NSF/DOE | \$125 | \$2,500 | contingency is for machined mounting fixtures | | \$125 | \$2,500 |
| 3.5 | Supplies | 1-Sep-2014 | 1-Oct-2014 | Labor | \$0 | | | all existing, do not expect to need | NSF/DOE | \$0 | \$100 | In case electrical tape or optical grease or ... needed... | | \$0 | \$100 |
| 3.6 | Construct frame for 1st prototype | 1-Sep-2014 | 30-Nov-2014 | parts & labor | \$1,000 | \$2,000 | | Estimate based on crude design, to produce in Rutgers machine shop | NSF/DOE | \$3,000 | \$1,000 | Only crude design exists, not costed by machine shop | \$840 | \$1,840 | \$1,000 |
| 3.7 | Test of available equipment at PSI | 1-Dec-2014 | 20-Dec-2014 | \$3,500 asked separately | | | | recent experience for 2-week trips to Switzerland | NSF/DOE | \$0 | \$300 | recent experience for trip costs variations | | \$0 | \$0 |
| 3.8 | Order first 5 more Photek MCP-PMT 240's | 1-Aug-2015 | 1-Dec-2015 | Equipment | \$107,500 | | | Photek quote, 1/24/2014 | NSF/DOE | \$107,500 | \$10,750 | | | \$107,500 | \$10,750 |
| 3.9 | Order 5 mounting fixtures | 1-Sep-2015 | 1-Oct-2015 | parts | \$125 | | | purchase of 3d printed mounting fixture in October 2013 | NSF/DOE | \$125 | \$2,500 | contingency is for machined mounting fixtures | | \$125 | \$2,500 |
| 3.10 | Dress rehearsal run at PSI | Nov 1, 2015 | Dec 20, 2015 | \$7,000 asked separately | | | | recent experience for 2 2-week trips to Switzerland | NSF/DOE | \$0 | \$600 | recent experience for trip costs variations | | \$0 | \$0 |
| 3.11 | Data analysis | Nov 1, 2015 | Feb 1, 2016 | | \$0 | | | existing manpower | | | | | | \$0 | \$0 |
| 3.12 | Design frame for 2nd Cerenkov | 1-Feb-2016 | 1-Apr-2016 | Labor | \$0 | | | | NSF/DOE | \$0 | | | | \$0 | \$0 |
| 3.13 | Construct frame for 2nd prototype | 1-Apr-2016 | 1-May-2016 | parts & labor | \$1,000 | \$2,000 | | Estimate based on crude design, to produce in Rutgers machine shop | NSF/DOE | \$3,000 | \$1,000 | | \$840.00 | \$1,840 | \$1,000 |
| 3.14 | install Cerenkov at PSI and commission | 1-May-2016 | 1-Jun-2016 | \$7,000 asked separately | | | | recent experience for 2 2-week trips to Switzerland | NSF/DOE | \$0 | \$600 | recent experience for trip costs variations | | \$0 | |
| | | | | | | | | | | | | | \$3,094 | \$205,494 | \$27,115 |

[illegible]

| WBS 5 | Cryogenic Hydrogen Target | start date | end date | M&S or Labor | M & S & E Cost | External Skilled Paid Labor | Employee / Student | BOE (labor is max estimated requirement for task) | Funding Source | Cost to Sponsor | Contingency | Reason for Contingency | Total | |
|--------|--|------------|------------|-----------------|----------------|-----------------------------|--------------------|--|----------------|-----------------|-------------|---------------------------------------|---|-----------|
| 5.1 | Bring Cryolab to Safe Operating State | 1-Mar-2014 | 1-Jun-2014 | Both | \$18,000 | \$5,000 | \$2,000 | Internal University Proposal | GWU | \$0 | \$25,000 | Internal Funding Not Approved | \$25,000 | |
| 5.1.1 | Design Drawings | 1-Mar-2014 | 1-Jul-2014 | Labor | \$0 | \$20,000 | \$0 | Average Cost to Other Projects | PSI | \$0 | \$25,000 | Need to use another designer | \$25,000 | |
| 5.1.2 | Order Instrumentation, Hardware, and Monitoring Devices | 1-Jul-2014 | 1-Sep-2014 | Both | \$135,000 | \$0 | | Adjusted Cost based on other recent projects | NSF/DOE | \$135,000 | \$31,050 | price fluctuations | \$166,050 | |
| 5.1.3 | Order Cryopump - Cold Head | 1-Jul-2014 | 1-Sep-2014 | Equipment | \$30,000 | \$0 | | Internet Price Listings and adjusted cost to other recent projects - asking for quotes | NSF/DOE | \$30,000 | \$6,900 | price fluctuations - design variation | \$36,900 | |
| 5.1.4 | Order Components of Motion System | 1-Jul-2014 | 1-Sep-2014 | Equipment | \$35,000 | \$0 | | Adjusted costs from other recent projects | NSF/DOE | \$35,000 | \$8,050 | price fluctuations - design variation | \$43,050 | |
| 5.1.5 | Order Material/Supplies for Scattering Chamber, Cell, Target Ladder, Holders and Railings | 1-Jul-2014 | 1-Sep-2014 | M&S | \$14,000 | \$0 | | Adjusted costs from other recent projects | NSF/DOE | \$14,000 | \$3,220 | price fluctuations - design variation | \$17,220 | |
| 5.1.6 | Prototype Cells and Cell Holders Machining and Assembly | 1-Sep-2014 | 1-Nov-2014 | Labor | \$0 | \$10,000 | | 200 hrs \$50/hrs = \$10,000 Machinist -- two months each Tech and Students | NSF/DOE | \$10,000 | \$2,300 | price fluctuations - design variation | \$12,300 | |
| 5.1.7 | Build Test Stand Chameber | 1-Sep-2014 | 1-Nov-2014 | Labor | \$0 | \$5,000 | | 100 hrs \$50/hrs = \$5,000 Machinist --- two months each Tech and Students | NSF/DOE | \$5,000 | \$1,150 | price fluctuations - design variation | \$6,150 | |
| 5.1.8 | Pressure, Vacuum, Destructive Tests of Cell Prototypes | 1-Nov-2014 | 1-Jan-2015 | Labor | \$0 | \$0 | | Two months each for Tech, Postdoc, Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.1.9 | Evaluation - Design Modification | 1-Jan-2014 | 1-Feb-2015 | Labor | \$0 | \$0 | | One month each for Tech, Postdoc, Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.1.10 | Prototype of Modified Cells | 1-Feb-2015 | 1-Mar-2015 | Labor | \$0 | \$5,000 | | 100 hrs \$50/hrs = \$5,000 Machinist --- one month each Tech, Post Doc and Students | NSF/DOE | \$5,000 | \$1,150 | | \$6,150 | |
| 5.1.11 | Second Round of Tests - Cold Test of Cells | 1-Mar-2015 | 1-Apr-2015 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.1.13 | Final Review of Design and Modifications | 1-Apr-2015 | 1-May-2015 | Labor | \$0 | \$2,000 | | 40 hrs \$50/hrs = \$2000 Machinist --- one month each Tech, Post Doc and Students | NSF/DOE | \$2,000 | \$460 | | \$2,460 | |
| 5.1.14 | Construction of Scattering Chamber | 1-May-2015 | 1-Jul-2015 | Labor | \$0 | \$10,000 | | 200 hrs \$50/hrs = \$10,000 Machinist -- one month each Tech and Students | NSF/DOE | \$10,000 | \$2,300 | price fluctuations - design variation | \$12,300 | |
| 5.2.1 | Construction of Cells | 1-May-2015 | 1-Jul-2015 | Labor | \$0 | \$10,000 | | 200 hrs \$50/hrs = \$10,000 Machinist -- one month each Tech and Students | NSF/DOE | \$10,000 | \$2,300 | price fluctuations - design variation | \$12,300 | |
| 5.2.2 | Tests of Cells and Scattering Chamber | 1-Jul-2015 | 1-Sep-2015 | Labor | \$0 | \$0 | | Two months each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.2.3 | Evaluation - Modifications | 1-Sep-2015 | 1-Oct-2015 | Labor | \$0 | \$5,000 | | 100 hrs \$50/hrs = \$5,000 Machinist --- one month each Tech, Post Doc and Students | NSF/DOE | \$5,000 | \$1,150 | | \$6,150 | |
| 5.2.4 | Second Round of Tests of Scattering Chamber and Cells Including motion test and test of emergency conditions | 1-Oct-2015 | 1-Dec-2015 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.2.5 | Evaluation and Readiness Review | 1-Dec-2015 | 1-Jan-2016 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| 5.2.6 | Construct Boxes for Shipping and Packing | 1-Jan-2016 | 1-Feb-2016 | Both | \$1,000 | \$2,000 | | 40 hrs Carpentry Shop -- One month each Tech and Students | NSF/DOE | \$3,000 | \$690 | price fluctuations - design variation | \$3,690 | |
| 5.2.7 | Shipping, Receiving and Unpacking | 1-Feb-2016 | 1-Mar-2016 | Both | \$2,000 | \$0 | | One month each Tech and Students | NSF/DOE | \$2,000 | \$460 | price fluctuations | \$2,460 | |
| 5.2.8 | In Situ Assembly and Testing | 1-Mar-2016 | 1-Apr-2016 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | design variation - unforeseen needs | \$0 | |
| 5.2.9 | PSI Safety Engineering Review and Modifications to Make Compliant | 1-Apr-2016 | 1-May-2016 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | design variation - unforeseen needs | \$0 | |
| 5.3 | Turn over to PSI | 1-May-2016 | 1-Jun-2016 | Labor | \$0 | \$0 | | One month each Tech, Post Doc and Students | NSF/DOE | \$0 | \$0 | | \$0 | |
| | | | | cost to project | \$217,000 | \$49,000 | \$2,000 | | | | \$266,000 | \$111,180 | Does not include Travel, Fringe and indirects | \$377,180 |

| WBS 6 | Electronics & DAQ | start date | end date | M&S or Labor | M & S & E Cost | External Skilled Paid Labor | Employee / Student | BOE | Funding Source | Cost to Sponsor | Contingency | Reason for Contingency | Total |
|-------|--|------------|-------------|-------------------|----------------|-----------------------------|--------------------|--|----------------|-----------------|-------------|---|-----------|
| 6.1 | Order first half of electronics | 1-Jun-2014 | 1-Dec-2014 | Labor & Equipment | \$195,514 | | | CAEN & GSI Quotes | NSF / DOE | \$195,514 | \$27,000 | EUR / USD exchange + loss of CAEN discount + possibly having to buy more expensive crates | \$222,514 |
| 6.2 | Organisation of mounting / power / infrastructure issues at PSI | 1-Mar-2014 | 1-Sep-2014 | Labor | | | | | NSF / DOE | \$0 | | | \$0 |
| 6.3 | Work on DAQ drivers & readout to improve speed | 1-Jul-2014 | 31-Jun-2016 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.4 | Receive delivery of electronics at PSI, and verify functionality | 1-Dec-2014 | 1-Mar-2015 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.5 | Mounting of electronics in "final" positions | 1-Feb-2015 | 1-Apr-2015 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.6 | Planning, prototyping and ordering cable components | 1-Apr-2015 | 1-Jun-2015 | L & E | \$10,800 | | \$3,200 | Estimates based on catalogue parts costs | NSF/DOE | \$14,000 | \$2,000 | Changing connector requirements / exchange rate estimates | \$16,000 |
| 6.7 | Cable manufacture, testing & installation, mounting on table where appropriate | 1-Jun-2015 | 1-Sep-2015 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.8 | Installation of DAQ software & integration of complete DAQ to read out all components. | 1-Aug-2015 | 1-Oct-2015 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.9 | Update quotes and place orders for remaining electronics | 1-Jun-2015 | 1-Aug-2015 | Labor | \$118,914 | | | CAEN & GSI Quotes | NSF/DOE | \$118,914 | \$22,000 | EUR / USD exchange + loss of CAEN discount + possibly having to buy more expensive crate | \$140,914 |
| 6.10 | Update quotes & place order for RAID array | 1-Jun-2015 | 1-Aug-2015 | Labor | \$88,291 | | | DELL Quote | NSF/DOE | \$88,291 | \$9,000 | 10% fluctuation due to price change / increased storage need | \$97,291 |
| 6.11 | Receive delivery of electronics & RAID Array at PSI, and verify functionality | 1-Dec-2015 | 1-Mar-2016 | Labor & Equipment | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.12 | Install electronics in final position and complete cabling | 1-Mar-2016 | 1-Apr-2016 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.13 | Install software and complete integration of new DAQ components | 1-Apr-2016 | 1-May-2016 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |
| 6.14 | Final testing & improvement of DAQ software | 1-May-2016 | 1-Jul-2016 | Labor | | | | | NSF/DOE | \$0 | | | \$0 |

| WBS-Code | Title | M&S | Labor | F&A | Contingency | Total w/o Contingency | Total with Contingency | BOE Quotes, past experience | Notes |
|----------|--|-----------------|-------------|----------|-------------|--------------------------|---------------------------|-----------------------------------|-----------------------------------|
| 7 | Scintillators | | | | | | | | |
| 7.1 | Design scint., beam mon., veto | | | | | \$0 | \$0 | | |
| 7.2 | Procure materials | | | | | \$0 | \$0 | | |
| 7.2.1 | Order scintillator | \$78,540 | | | \$12,566 | \$78,540 | \$91,106 | | |
| 7.2.2 | Order PMTs | \$187,272 | | | \$28,091 | \$187,272 | \$215,363 | | |
| 7.2.3 | Order Supplies | \$18,058 | \$0 | \$0 | \$3,431 | \$18,058 | \$21,489 | | |
| 7.2.4 | Order backing structure | \$44,215 | | | \$9,285 | \$44,215 | \$53,500 | | |
| 7.2.5 | Order shipping crates | \$3,600 | \$21,600 | \$1,188 | \$5,541 | \$26,388 | \$31,929 | | include shipping cost in labor |
| 7.3 | Construction | | | | | \$0 | \$0 | | |
| 7.3.1 | Test PMTs | | | | | \$0 | \$0 | | |
| 7.3.2 | Beam Monitor | | | | | \$0 | \$0 | | |
| 7.3.3 | Veto Detector | | | | | \$0 | \$0 | | |
| 7.3.4 | TOF-batch 1 | | | | | \$0 | \$0 | | |
| 7.3.5 | TOF-batch 2 | | | | | \$0 | \$0 | | |
| 7.3.6 | TOF-batch 3-8 | | | | | \$0 | \$0 | | |
| 7.3.7 | Beam Mon, Veto first half TOF ready | | | | | \$0 | \$0 | | |
| 7.3.8 | TOF-batch 9-12 | | | | | \$0 | \$0 | | |
| 7.3.9 | TOF-batch 12-16 | | | | | \$0 | \$0 | | |
| 7.3.10 | TOF second half ready | | | | | \$0 | \$0 | | |
| 7.4 | Shipping | | | | | \$0 | \$0 | | |
| 7.4.1 | Ship first half | | | | | \$0 | \$0 | | |
| 7.4.2 | Ship second half | | | | | \$0 | \$0 | | |
| | Labor | | \$67,735 | \$19,952 | \$9,646 | \$87,687 | \$97,333 | | |
| | Total | \$331,685 | \$89,335 | \$21,140 | \$68,561 | \$442,160 | \$510,721 | | |
| | | GS | | | | | | | |
| | Labor | stipend+tuition | UG salaries | Fringe | | | | | |
| | | \$30,275 | \$32,832 | \$4,628 | | | | | |

| WBS 8 | GEM detectors | start date | end date | M&S or Labor | Cost | BOE | F&A | cottingency |
|-------|--------------------------------------|------------------|-------------------|--------------|----------|-------------------------------|---------|-------------|
| 8.1 | Purchase of spare electronics | | | | | | | |
| 8.1.1 | Order 2 VME crates | 1-Jul-14 | 1-Oct-14 | Equipment | \$14,464 | Quote/previous order | | \$2,459 |
| 8.1.2 | Order 2 VME CPUs | 1-Jul-14 | 1-Oct-14 | Equipment | \$6,170 | Quote/previous order | | \$1,049 |
| 8.1.3 | Order 2 MPDs | 1-Jul-14 | 1-Oct-14 | Equipment | \$6,300 | Quote | | \$1,071 |
| 8.1.4 | Supplies for cabeling and connectors | 1-Jul-14 | 1-Oct-14 | Supplies | \$1,500 | Estimated | \$720 | \$255 |
| 8.2 | Establish fast readout | | | | | | | \$0 |
| 8.2.1 | Commission new electronics | 1 week after D6 | 2 weeks after C9 | | | Time per piece | | \$0 |
| 8.2.2 | Make cables | 1 week after D6 | 4 weeks after C9 | | | | | \$0 |
| 8.2.3 | Test combined system | 1 week after D10 | 4 weeks after C11 | | | | | \$0 |
| 8.3 | Ship 2 crates | 1 week after D11 | 4 weeks after C12 | | \$2,000 | estimated / previous shipment | \$960 | \$340 |
| | Total | | | | \$30,434 | 0 | \$1,680 | \$5,174 |

| WBS 9 | Item | Labor | F&A | Contingency | |
|-------|---|-----------|-----------|-------------|---|
| | | | | | |
| | Rutgers Post-doc on site for preparations, years 1 and 2 | \$206,700 | \$53,742 | \$15,627 | stipend, \$75,000/year, fringe 37.8%, F&A 26% |
| | Rutgers Post-doc on site for running expt, years 3 and 4 | \$219,102 | \$56,967 | \$16,564 | 6% increase in salary |
| | total | \$425,802 | \$110,709 | \$32,191 | |

Procedure for Estimating Contingency

January 24, 2006

This document gives the procedure for estimating contingencies on the MINERvA project. There are different procedures, depending on if the task is predominantly M&S or if it is Labor. The M&S contingency table is the one that has been adopted by BABAR. The labor contingency tables have been developed by Bob Bradford and Deborah Harris.

The most important part of filling out these tables is that it forces you to think about the risks. If after filling out the table you get a contingency you are not comfortable with, simply include that in the BOE and provide the contingency you are comfortable with, and a justification (i.e. imagine you are constrained to hire a full extra person for the job if it takes more effort than expected: then the contingency would have to cover one extra person, not just a fraction of a person).

I. M&S Contingency

| Factor (R) | Technical | Design | Cost | Schedule |
|---------------|--|---|---|--|
| 0 | Not used | Detailed design more than 50% complete | Not used | |
| 1 | Existing Design; off the shelf hardware | Not used | Off-the-shelf or catalog item | Not used |
| 2 | Minor modifications to an existing design | Not used | Vendor quote from established drawings | Not used |
| 3 | Extensive modifications to an existing design | Not used | Vendor quote with some design sketches | No schedule impact on any other item |
| 4 | New design; nothing exotic | Preliminary design more than 50% complete; some analysis done | In-house estimate based on previous experience | Not used |
| 6 | New design; different from established designs; existing technology | Not done | In-house estimate for item with minimal experience but related to existing capabilities | Delays completion of non-critical subsystem item |
| 8 | New design; requires some R&D, but does not advance the state of the art | Conceptual design phase; some drawings; many sketches | In-house estimate for item with minimal experience and minimal in-house capability | Delays completion of critical subsystem item |
| 10 | New design; development of new technology; advances state-of-the art | Not used | Top-down estimate from analogous programs | Not used |
| 15 | New design; well beyond current state-of-the-art | Concept only | Engineering judgment | Not used |
| Weight | 2% | 2% | 1% | 1% |

Example: (yellow indicates calculated values)

| | | | | | | |
|------------|-----------|--------|------|----------|-------|---------|
| Total Cost | Technical | Design | Cost | Schedule | Total | Cont |
| 10000 | 4 | 15 | 4 | 8 | 0.5 | \$5,000 |

II. Labor Contingency

Labor Contingency is evaluated differently, depending on if the task is to be performed once (like designing a detector stand), or if it is to be performed many times (like assembling a scintillator plane). In either case there are four categories that should be evaluated, and the contingency is again the sum of the Risk factor times the weight. The following two tables give the guidance for non-repetitive and repetitive tasks. A detailed explanation of the repetitive task categories follows the last table.

A. Labor Contingency Estimator: Non-repetitive Tasks

| Factor (R) | Personnel Experience | Procedure Definition | Similarity to Prior Work | Task Duration |
|------------|--|---------------------------------|--|---------------|
| 1 | Experienced professional who has done this before | Design and procedures finalized | Identical work in the past at this institution | 2 years |
| 3 | Experienced professional who hasn't done this before | Well-defined process | Identical work done at other institution | 6 months |
| 7 | New professional | Some details understood | Similar work done at this facility | 2 months |
| 10 | Undergraduate or graduate | Conceptual only | Similar work done at different facility | 2 weeks |
| 15 | Summer student | None exists | None | Few days |
| Weight | 2% | 2% | 1% | 1% |

$$\%C = \sum_i R_i W_i$$

Example: (yellow indicates calculated values)

| | | | | | | |
|------------|----------------------|----------------------|--------------------------|---------------|-------|-------------|
| Total Cost | Personnel Experience | Procedure Definition | Similarity to Prior Work | Task Duration | Total | Contingency |
| 10000 | 4 | 15 | 4 | 3 | 0.45 | \$4,500 |

B. Labor Contingency Estimator: Repetitive Tasks

| Factor | Startup | Duration Estimate | Reliance on Vendors | Task Duration |
|--------|--|---|--|---------------|
| 1 | Task rehearsed; experienced crew | Estimate from similar experience | (1) Vendors reliable; (2) significant float before item(s) needed; (3) can easily find alternate vendor. | 2 years |
| 3 | Minor recent changes to protocol; some new labor. | Estimate from related experience with minor differences. | Vendor reasonably reliable, but not replaceable. Reasonable float in schedule. | 6 months |
| 7 | Significant changes to protocol or to labor | Estimate from experience with understood but significant differences. | Vendor reasonably reliable, but not replaceable. Not much float in schedule. | 2 months |
| 10 | Significant changes to protocol and significant new hires. | Engineer's estimate | Vendors unreliable (task not prototyped); and not replaceable. Minimal schedule float. | 2 weeks |
| 15 | Procedure unrehearsed; entirely new crew. | Physicist's estimate | Vendor unreliable (WBS task not prototyped); Minimal schedule float, item on/near critical path. | Few days |
| Weight | 2 | 1 | 1 | 1 |

$$\%C = \sum_i R_i W_i$$

Example: (yellow indicates calculated values)

| Total Cost | Startup | Duration Estimate | Reliance on Vendors | Task Duration | Total | Contingency |
|------------|---------|-------------------|---------------------|---------------|-------|-------------|
| 1000 | 4 | 15 | 4 | 3 | 0.3 | \$300 |

Repetitive Task Contingency Categories:

1. **Startup:** With repetitive tasks, delays are most likely related to an under-estimated startup time. It's always the first few units that will require the most time – building the first module or assembling the first PMT box. During startup, the labor are still familiarizing themselves with the production process, and they are relatively unskilled. By the time a few units has been produced, everyone is an expert, bugs in the production process have been addressed, and things should be moving along smoothly. Chances for contingency here are going to be related to the experience of the workforce and the procedural definition of the task. For example: How much of the your labor force was newly hired for the job? Did any of the workers help construct prototypes? How closely did the prototype resemble the final product? Have there been any significant changes in tooling or the production process since the prototyping effort?
2. **Duration Estimate:** This category deals with the rate of production after startup. Ideally, total durations for a long-term production process are based on some assumed rate (i.e. – assembling 5 PMT boxes per week, building 1 scintillator plane per day). This rate is scaled by the total number of deliverables to produce the total task duration. How certain are you of the rate? Did you estimate the rate from prototyping? If so, how realistic was the prototyping effort? Did you scale from MINOS? Is this an engineer's estimate? A physicist's estimate? Granted, the last two estimates are "rough": clearly not all physicists warrant the same contingency factor, nor do all engineers.
3. **Reliance on vendors:** Links to other WBS tasks (or vendors) pose risks to a schedule. For example, module assembly relies on delivery of steel frames from WBS8 and packaged scintillator from WBS3. Will a delay in shipment of a delivery impact your schedule? You might consider how reliable a vendor has been in the past, or how complex the component is you are receiving (Are you waiting on stock steel tubing, or is the deliverable more complex)? If there is a significant delay, can you find an alternate vendor? Also, what is the delivery schedule? If all shipments are to be received before you open your factory, then you minimize contingency due to a vendor delay. If the deliverables come in multiple shipments, with some shipments coming after your factory is running, then you risk having a cost contingency (standing army problem) in the event of a delay.
4. **Duration of task:** This is the length of your 85% CL task duration that goes into project. Longer tasks have more flexibility in overcoming vendor delays, bad startups, etc.

| Defined Conditions for Impact Scales of a Risk on Major Project Objectives (Examples are shown for negative impacts only) | | | | | |
|---|--|---|---|---|---|
| Project Objective | Relative or numerical scales are shown | | | | |
| | Very low /.05 | Low /.10 | Moderate /.20 | High /.40 | Very high /.80 |
| Cost | Insignificant cost increase | <10% cost increase | 10-20% cost increase | 20-40% cost increase | >40% cost increase |
| Time | Insignificant time increase | <5% time increase | 5-10% time increase | 10-20% time increase | >20% time increase |
| Scope | Scope decrease barely noticeable | Minor areas of scope affected | Major areas of scope affected | Scope reduction unacceptable to sponsor | Project end item is effectively useless |
| Quality | Quality degradation barely noticeable | Only very demanding applications are affected | Quality reduction requires sponsor approval | Quality reduction unacceptable to sponsor | Project end item is effectively useless |
| This table presents examples of risk impact definitions for four different project objectives. They should be tailored in the Risk Management Planning process to the individual project and to the organization's risk thresholds. Impact definitions can be developed for opportunities in a similar way. | | | | | |

Figure 11-5. Definition of Impact Scales for Four Project Objectives

Probability and Impact Matrix

| Probability | Threats | | | | | Opportunities | | | | |
|-------------|---------|------|------|------|------|---------------|------|------|------|------|
| 0.90 | 0.05 | 0.09 | 0.18 | 0.36 | 0.72 | 0.72 | 0.36 | 0.18 | 0.09 | 0.05 |
| 0.70 | 0.04 | 0.07 | 0.14 | 0.28 | 0.56 | 0.56 | 0.28 | 0.14 | 0.07 | 0.04 |
| 0.50 | 0.03 | 0.05 | 0.10 | 0.20 | 0.40 | 0.40 | 0.20 | 0.10 | 0.05 | 0.03 |
| 0.30 | 0.02 | 0.03 | 0.06 | 0.12 | 0.24 | 0.24 | 0.12 | 0.06 | 0.03 | 0.02 |
| 0.10 | 0.01 | 0.01 | 0.02 | 0.04 | 0.08 | 0.08 | 0.04 | 0.02 | 0.01 | 0.01 |
| | 0.05 | 0.10 | 0.20 | 0.40 | 0.80 | 0.80 | 0.40 | 0.20 | 0.10 | 0.05 |

Impact (ratio scale) on an objective (e.g., cost, time, scope or quality)

Each risk is rated on its probability of occurring and impact on an objective if it does occur. The organization's threshold for low, moderate or high risks are shown in the matrix and determine whether the risk is scored as high, moderate or low for that objective.