



MUSE Project Management

Ronald Ransome

Rutgers

The State University of New Jersey

For the MUSE Collaboration




Outline

- ◆ Project WBS Organization
- ◆ Overall Schedule
- ◆ Assessment of each WBS
- ◆ Contingency management



WBS

- ◆ There are 8 construction elements
- ◆ We've included a catch-all "Installation" element
 - ▼ This will contain miscellaneous work to be done before and after installation, as well as installation milestones
- ◆ The Gantt chart also has a WBS 10 (Funding) which is simply for convenience of linking tasks to the funding schedule





WBS Dictionary

WBS	Institution	Scope
1	Rutgers	Build support table and frames for detectors
2	Tel Aviv	Scintillating Fiber Detector
3	Rutgers	Cerenkov Detector
4	Hebrew	Straw Chambers
5	GWU	LH2 Target
6	GWU	Electronics and DAQ
7	S.Carolina	Scintillators
8	Hampton	GEM detectors

Each WBS is independent of the others
until final assembly, except some
electronics needed for testing



Schedule

- ◆ Two major milestones:
 - ▼ Test run in fall 2015
 - ▼ Full run in fall 2016
- ◆ Items needed for 2015 Run
 - ▼ Support Table (WBS1) - by June (anticipated by March 2015)
 - ▼ GEMs (already there)
 - ▼ Half of Cerenkov (WBS3) - by July (by January 2015)
 - ▼ Half of Scintillator (WBS7), Veto - by August (by August 2015)
 - ▼ Sci-Fi detector (WBS2) - by September (by August 2015)
 - ▼ Straw tube - 1 chamber (WBS4) - by October (by June 2015)
 - ▼ Half of electronics (WBS6) - with associated detector (by July 2015)
 - ▼ Does not need LH2



Budget & Contingency

- ◆ Each WBS has a combination of labor and equipment.
- ◆ Equipment is mainly standard, from well known designs, or off-the-shelf.
 - ▼ Largest uncertainties come from currency exchange risks
- ◆ Labor is mainly in salaried employees (i.e. grad students, post-docs, full time tech), not hourly. This gives some less uncertainty in costs.

Does not include F&A or contingency WBS	Quotes, recent purchases	from similar projects	more uncertain		
	Material-Firm	Material-medium	Other Material	%Firm	%Firm/Med
1-table	\$0	\$13,205	\$0	0.0%	100.0%
2-Sci-Fi	\$33,134	\$32,000	\$0	50.9%	100.0%
3-Cerenkov	\$200,150	\$0	\$2,250	98.9%	98.9%
4-Straw	\$55,737	\$268,450	\$19,000	16.2%	94.5%
5-Cryo	\$0	\$217,000	\$0	0.0%	100.0%
6-Electronics	\$402,719	\$14,000	\$0	96.6%	100.0%
7-Scintillator	\$265,812	\$65,873	\$0	80.1%	100.0%
8-GEM	\$26,934	\$3,500	\$0	88.5%	100.0%
Total	\$984,486	\$614,028	\$21,250	60.8%	98.7%
	GS/PD	Technician/UG	Shop, uncertain times		
	Wages-Firm	Wages-medium	Other Wages	%Firm	%Firm/Med
1-table	\$0	\$10,347	\$0	0.0%	100.0%
2-Sci-Fi	\$50,000	\$20,000	\$0	71.4%	100.0%
3-Cerenkov	\$0	\$0	\$4,000	0.0%	0.0%
4-Straw	\$115,236	\$0	\$21,000	84.6%	84.6%
5-Cryo	\$146,916	\$190,512	\$49,000	38.0%	87.3%
6-Electronics	\$149,460	\$0	\$0	100.0%	100.0%
7-Scintillator	\$0	\$67,735	\$0	0.0%	100.0%
8-GEM	\$0	\$0	\$0	0.0%	0.0%
Total	\$461,612	\$288,594	\$74,000	56.0%	91.0%



Travel

- ◆ Travel is a major expense
 - ▼ Meetings (~\$40K/year)
 - ▼ Installation/testing 2015 (~\$250K)
 - ▼ Running 2016 onward (~\$350K/year)



WBS

- ◆ I will discuss major cost components, schedule, and risks for the WBS 2,3,4,7.
- ◆ WBS 1 consists of low cost construction with very low construction, technical, or schedule risk
- ◆ WBS 8 consists of minor backup to working system
- ◆ WBS 5,6 discussed earlier today
- ◆ WBS 9 currently has a primary cost of an on-site post-doc



WBS 4 - Straw Tubes

◆ Major Cost Items

▼ Straws

- Straws & wire BOE - quote \$24K
- Hardware (pins, caps) BOE - PANDA experience - \$327K
- Contingency \$146K

▼ Labor

- Salaried - 2 GS (one from HU, one from Temple)
- \$175K (includes travel for Temple student)
- Contingency \$35K

▼ Total Cost \$637K +\$202K contingency



WBS 4 - Schedule

◆ Set up

- ▼ Requires mounting table, clean room
- ▼ Estimated Completion date - August 2014

◆ Straw Construction

- ▼ Estimated at least 25/week
- ▼ First chamber completed - May, 2015
- ▼ Chamber 2-4 completed - January 2016



WBS4

4	Straw Chambers		87	135	1.83 years	7/2/14	3/8/16
4.1	Order straw material	6 months	11		6 months	7/2/14	12/16/14
4.2	Order gas system	2 months	118		2 months	7/2/14	8/26/14
4.3	Set up clean room	2 months	57	135	2 months	7/2/14	8/26/14
4.4	Manufacture Jigs	2 months	111	135	2 months	7/2/14	8/26/14
4.5	Design chamber mounting	2 months	127	135	2 months	7/2/14	8/26/14
4.6	manufacture straws ch 1	2 months	75	56; 58; 59	2 months	12/17/14	2/10/15
4.7	manufacture gas dist.	2 months	95	57	2 months	8/27/14	10/21/14
4.8	machine chamber mounting	2 months	6	60	2 months	8/27/14	10/21/14
4.9	assemble & test ch 1	2 months	65	61; 63	2 months	2/11/15	4/7/15
4.10	ship to PSI	1 month	69	64	1 month	4/8/15	5/5/15
4.11	Commission ch 1 at PSI	1 month	97	65	1 month	5/6/15	6/2/15
4.12	Ch 1 ready at PSI		19	66	0 hours	6/2/15	6/2/15
4.13	Purchase 2nd gas system	1 month	21	61	1 month	2/11/15	3/10/15
4.14	Build ch 2-4	9 months	119	64	9 months	4/8/15	12/15/15
4.15	Ship ch 2-4 to psi	1 month	2	69	1 month	12/16/15	1/12/16
4.16	Commision at PSI	2 months	79	70	2 months	1/13/16	3/8/16



WBS 4 - QA and Risk

◆ QA

- ▼ Straws will be tested with source, planes with cosmics
- ▼ Pressure testing as straws are built

◆ Major Risks

- ▼ Higher than anticipated failure rate
 - Close consultation with PANDA to conform to proven procedures
 - Buy enough extra parts to mitigate small batch costs/time delay
 - We will buy 4000 straws at outset, and parts for 3500, with contingency for 500 more sets of parts



WBS 7 - Scintillator

◆ Major Costs

- ▼ PMTs - BOE quote - \$187K
- ▼ Scintillator - BOE quote - \$78K
- ▼ Backing structure - BOE quote \$44K
- ▼ Labor - BOE past experience - \$110K

◆ Total Cost \$442K + \$72K contingency



WBS 7 - Schedule

- ◆ Pre-construction - order PMT's and scintillator (2-3 months)
- ◆ Scintillators are made in batches of 6, with one set completed before moving on.
- ◆ Need to place orders by July 2014 to be ready for fall 2015 run.
- ◆ Full set completed by early 2016, no risk on full run



WBS7

7	Scintillators		31			2.15 years	4/1/14	3/22/16
7.1	Design scint., beam mon., veto	1 month	146		4/1/14	1 month	4/1/14	4/28/14
7.2	Procure materials		134	135FS+1 month		10.85 months	7/30/14	5/28/15
7.2.1	Order scintillator	2 months	136			2 months	7/30/14	9/23/14
7.2.2	Order PMTs	2 months	135			2 months	7/30/14	9/23/14
7.2.3	Order Supplies	1 month	145			1 month	7/30/14	8/26/14
7.2.4	Order backing structure	1 month	144		5/1/15	1 month	5/1/15	5/28/15
7.2.5	Order shipping crates	1 month	142		5/1/15	1 month	5/1/15	5/28/15
7.3	Construction		133			1.58 years	9/24/14	3/8/16
7.3.1	Test PMTs	1.25 months	140	105		1.25 months	9/24/14	10/28/14
7.3.2	Beam Monitor	2 months	138	110		2 months	10/29/14	12/23/14
7.3.3	Veto Detector	2 months	137	111		2 months	12/24/14	2/17/15
7.3.4	TOF-batch 1	1.5 months	143	112		1.5 months	2/18/15	3/31/15
7.3.5	TOF-batch 2	1.5 months	139	113		1.5 months	4/1/15	5/12/15
7.3.6	TOF-batch 3-8	2.75 months	141	114		2.75 months	5/13/15	7/28/15
7.3.7	Beam Mon, Veto first half TOF ready		147	115		0 hours	7/28/15	7/28/15
7.3.8	TOF-batch 9-12	4 months	149	115		4 months	7/29/15	11/17/15
7.3.9	TOF-batch 12-16	4 months	148	117		4 months	11/18/15	3/8/16
7.3.10	TOF second half ready		150	118		0 hours	3/8/16	3/8/16
7.4	Shipping		151			8.5 months	7/29/15	3/22/16
7.4.1	Ship first half	0.5 months	153	116		2 weeks	7/29/15	8/11/15
7.4.2	Ship second half	0.5 months	152	118		2 weeks	3/9/16	3/22/16



WBS 7 - QA & Risk

- ◆ QA - scintillators checked with source and cosmics before shipping
- ◆ Risks
 - ▼ low technical risk, this is a proven technology
 - ▼ Some schedule risk for 2015 test run if material is delayed in arriving. Would require using smaller number for test, additional shipping costs.
 - ▼ Some design risk, may increase size slightly if decision is made to move farther back (<10% cost)



WBS 2 SciFi

◆ Major costs

- ▼ Fiber - BOE quotes - \$12K
- ▼ PMT - BOE quotes - \$23 K
- ▼ PMT bases, supplies - BOE past experience - \$32K
- ▼ Labor - GS \$70 K
- ▼ Total - \$152K plus \$29K contingency



WBS2

2	Scintillating Fiber		40		1.21 years	7/2/14	8/11/15
2.1	Order Materials		99	135	6 months	7/2/14	12/16/14
2.1.1	Order Fiber	6 months	64		6 months	7/2/14	12/16/14
2.1.2	Order PMTs	6 months	53		6 months	7/2/14	12/16/14
2.1.3	Order tools	2 months	107		2 months	7/2/14	8/26/14
2.2	Prototype	1 month	112	32	1 month	12/17/14	1/13/15
2.3	Construct fibers	3 months	16	36	3 months	1/14/15	4/7/15
2.4	Mount fibers	1 month	43	37	1 month	4/8/15	5/5/15
2.5	Testing	1 month	76	38	1 month	5/6/15	6/2/15
2.6	Ship to PSI	2 weeks	20	39	2 weeks	6/3/15	6/16/15
2.7	Test at PSI	2 months	59	40	2 months	6/17/15	8/11/15



WBS 2 Schedule, QA, Risk

- ◆ Easily completed in 6 months after materials arrive
- ◆ Will be tested with source and cosmics
- ◆ No schedule risk
- ◆ Low technical risk, proven technology



WBS 3 - Cerenkov

- ◆ Major Cost
 - ▼ PMTs - BOE quote - \$195K
 - ▼ Total cost \$212 K plus \$27 contingency
- ◆ Schedule - easily assembled in 2 months after materials arrive
- ◆ QA - cosmic and beam tests
- ◆ No schedule risk
- ◆ Low technical risk, proven technology



WBS3

3	Cerenkov		105		1.87 years	2/3/14	10/21/15
3.1	Design Cerenkov	5 months	85		5 months	2/3/14	6/20/14
3.2	Buy materials first part		77	135	4 months	7/2/14	10/21/14
3.2.1	Buy first 4 tubes	4 months	109		4 months	7/2/14	10/21/14
3.2.2	Buy sapphire	3 months	73		3 months	7/2/14	9/23/14
3.2.3	Buy assembly materials	1 month	45		1 month	7/2/14	7/29/14
3.3	Assemble	2 months	33	44	2 months	10/22/14	12/16/14
3.4	Ship to PSI	1 month	13	48	1 month	12/17/14	1/13/15
3.5	First set at PSI		51	49	0 hours	1/13/15	1/13/15
3.6	Buy 5 tubes	4 months	9	136	4 months	7/2/15	10/21/15
3.7	Buy mounting fixtures	1 month	34	136	1 month	7/2/15	7/29/15
3.8	Frame for 2nd cerenkov	2 months	71	52	2 months	7/30/15	9/23/15
3.9	Install at PSI	1 month	90	53	1 month	9/24/15	10/21/15



Handling Contingency

◆ Plans for handling contingency

▼ M&S/Labor Contingency

- <\$5K up to WBS manager
- \$5-25 K up to Project Manager
- >\$25 K must be reviewed by managers for impact on scope and schedule, approval by Project Manager

▼ Travel Contingency

- Any anticipated change over \$2 K must be approved by Project Manager
- Must take into account importance to set-up, construction, maintaining experiment (e.g. move to set-up travel out of collaboration meeting travel)



Schedule & Reporting

- ◆ Schedule will be reviewed once date is know for funding
 - ▼ Set milestones
- ◆ Determine funding distribution based needs to prioritize test run 2015
- ◆ Each WBS manager will report project progress to Project Manager on a bi-monthly basis.



WBS 1

1	Frames & Design		7		1.87 years	3/1/14	11/18/15
1.1	Table		36		1.12 years	3/1/14	3/13/15
1.1.1	Design table	9 months	47	3/1/14	9 months	3/1/14	11/7/14
1.1.2	Buy table parts		125	3; 135	1 month	11/10/14	12/5/14
1.1.2.1	rotary bearings	1 month	92		1 month	11/10/14	12/5/14
1.1.2.2	extrusions for frame	1 month	4		1 month	11/10/14	12/5/14
1.1.2.3	linear bearings	1 month	67		1 month	11/10/14	12/5/14
1.1.3	Machine & assemble table		74	4	1.5 months	12/8/14	1/16/15
1.1.3.1	machine donuts and table	1 month	30		1 month	12/8/14	1/2/15
1.1.3.2	machine extrusions	1 month	98		1 month	12/8/14	1/2/15
1.1.3.3	assemble table	2 weeks	91	9; 10	2 weeks	1/5/15	1/16/15
1.1.4	Ship and assemble table		60		2 months	1/19/15	3/13/15
1.1.4.1	Ship to PSI	1 month	113	8	1 month	1/19/15	2/13/15
1.1.4.2	Assemble table at PSI	1 month	1	13	1 month	2/16/15	3/13/15
1.2	Table ready at PSI		86	14	0 hours	3/13/15	3/13/15
1.3	Scintillator and Veto		48		1.42 years	7/1/14	10/21/15
1.3.1	Design scintillator frames	6 months	96	7/1/14	6 months	7/1/14	12/15/14
1.3.2	Build first scintillator frame	2 months	66	17; 135	2 months	12/16/14	2/9/15
1.3.3	Ship first frames to PSI	1 month	54	18	1 month	2/10/15	3/9/15
1.3.4	Build second scint. frames	2 months	38	18; 136	2 months	7/2/15	8/26/15
1.3.5	Ship second set to PSI	1 month	120	20	1 month	8/27/15	9/23/15
1.3.6	Assemble at PSI	1 month	80	21	1 month	9/24/15	10/21/15
1.3.7	Veto design	2 months	8	17	2 months	12/16/14	2/9/15
1.3.8	Build veto	1 month	103	23	1 month	2/10/15	3/9/15
1.3.9	Ship veto to PSI	1 month	14	24	1 month	3/10/15	4/6/15
1.4	Beam Monitor		68		5 months	7/2/15	11/18/15
1.4.1	Design beam monitor	2 months	61	23; 136	2 months	7/2/15	8/26/15
1.4.2	Build beam monitor	1 month	15	27	1 month	8/27/15	9/23/15
1.4.3	Ship to PSI	1 month	122	28	1 month	9/24/15	10/21/15
1.4.4	Assemble PSI	1 month	42	29	1 month	10/22/15	11/18/15



WBS5

5	Cryo-target		37	↗		2.28 years	3/1/14	4/5/16
5.1	Set up lab	3 months	28	↗	3/1/14	3 months	3/1/14	5/23/14
5.2	Do Design	4 months	55	↗	3/1/14	4 months	3/1/14	6/20/14
5.3	Order major elements	2 months	25		74; 135	2 months	7/2/14	8/26/14
5.4	Construct prototype	2 months	56		75	2 months	8/27/14	10/21/14
5.5	Test and eval. of prototype	2 months	5		76	2 months	10/22/14	12/16/14
5.6	Redesign and 2nd proto.	2 months	115		77	2 months	12/17/14	2/10/15
5.7	Test and final design	2 months	46		78	2 months	2/11/15	4/7/15
5.8	Target Cell design		23		79	0 hours	4/7/15	4/7/15
5.9	Const. Scatt. Chamb. & cells	2 months	82		79	2 months	4/8/15	6/2/15
5.10	Test and Evaluate	3 months	29		81	3 months	6/3/15	8/25/15
5.11	Test complete system	2 months	10		82	2 months	8/26/15	10/20/15
5.12	Review	1 month	72		83	1 month	10/21/15	11/17/15
5.13	Ship and set up	2 months	93		84	2 months	11/18/15	1/12/16
5.14	In situ testing	1 month	108		85	1 month	1/13/16	2/9/16
5.15	Final review	2 months	24		86	2 months	2/10/16	4/5/16
5.16	Ready to Run		117		87	0 hours	4/5/16	4/5/16
6	Electronics & DAQ		17			2.17 years	7/2/14	6/28/16



WBS6

6.1	Order first half electronics	6 months	52	135	6 months	7/2/14	12/16/14
6.2	Mounting/order cables	2 months	114	90	2 months	12/17/14	2/10/15
6.3	Manufacture/Install cables	2 months	44	91	2 months	2/11/15	4/7/15
6.4	Develop DAQ	1 year	130	135	1 year	7/2/14	6/2/15
6.5	Install and test complete DAQ	2 months	62	92; 93	2 months	6/3/15	7/28/15
6.6	DAQ ready for test run		129	94	0 hours	7/28/15	7/28/15
6.7	Order 2nd half electronics	6 months	102	136	6 months	7/2/15	12/16/15
6.8	Optimize DAQ	1 year	131	94	1 year	7/29/15	6/28/16
6.9	Install and complete DAQ	3 months	12	96	3 months	12/17/15	3/9/16
6.10	Final test of DAQ	3 months	58	98	3 months	3/10/16	6/1/16
6.11	Write initial analysis program	1 year	132	135	1 year	7/2/14	6/2/15